

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
502		ADAMS	315	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

\* (53RS-7,P(RS-2))N,TS  
CONTRACT NO. 72897

ROAD CONSTRUCTION SCHEDULE - BY STAGES						
PAY ITEM	STAGE I	STAGE II	STAGE III	STAGE IV	STAGE V	TOTALS
GUTTER REMOVAL- FOOT	1522	1302				2824
DRIVEWAY PAVEMENT REMOVAL- SQ YD	431	894				1325
TEMPORARY BITUMINOUS PAVEMENT- SQ YD	6652	2614				9266
PAVEMENT REMOVAL - SQ YD		6225	750	510		7485
BITUMINOUS SHOULDER REMOVAL- SQ YD		1024				1024
TEMPORARY PAVEMENT REMOVAL - SQ YD			6652		2614	9266
PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) - SQ YD		6577	6815	803	80	14275
PORTLAND CEMENT CONCRETE SHOULDERS 10" - SQ YD		815	1041	46	333	2235
SUB-BASE GRANULAR MATERIAL, TYPE B 12"- SQ YD		7392	7856	849	1801	17898
SUB-BASE GRANULAR MATERIAL, TYPE C 4" - SQ YD		815	1041	46	333	2235
STABILIZED SUB-BASE 4" - SQ YD		6577	6815	803	1468	15663
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 - FOOT		97	370	45		512
CONCRETE GUTTER, TYPE A - FOOT		687	1202	55		1944
PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH - SQ YD		75	755			830
BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50 - TONS				23		23
BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90 - TONS				44		44
BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70 - TONS				36		36
BITUMINOUS SHOULDERS SUPERPAVE 10" - SQ YD				130		130
CONCRETE MEDIAN, TYPE SM- 6.06 - SQ FT					10366	10366
CORRUGATED MEDIAN - SQ FT					1784	1784
CONCRETE MEDIAN SURFACE 4" - SQ FT					167	167
COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 - FOOT					28	28
COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 - FOOT					26	26
COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 ( VARIABLE WIDTH GUTTER FLAG) - FOOT					27	27
AGGREGATE SHOULDERS, TYPE B - TONS					62	62

INLET SCHEDULE -EACH					
LOCATION	IN, SPEC, TY A, TY 15, FR & G	IN, TY B, TY 8, FR & G	IN, TY B, TY 9, FR & G	IN, TY A, TY 15, FR & G	INLET TO BE ADJUSTED
ST 1 - 144+75.00, 14.88' rt	1				
ST 5 - 147+25.00, 11.40' rt	1				
ST 2 - 144+75.00, 40.00' rt		1			
ST 3 - 145+25.00, 46.30' rt		1			
ST 6 - 148+75.00, 58.50' rt		1			
ST 9 - 72+05.50, 39.70' rt			1		
ST 10 - 72+06.00, 19.50' rt				1	
IL 57 - 72+06.00, 21.00' lt					1
<b>TOTALS</b>	<b>2</b>	<b>3</b>	<b>1</b>	<b>1</b>	<b>1</b>

MANHOLE SCHEDULE - EACH			
LOCATION	MH, TY A 4' DIA TY 8 FR & G	MH, TY A 4' DIA TY 1 FR, CL	MH, TY A 4' DIA TY 9, FR & G
141+90.00, 30' rt	1		
ST 7 - 70+41.95, 67.8' rt	1		
142+31.00, 32' rt		1	
72+05.00, 46' rt		1	
ST 4 147+25.00, 51.50' rt			1
<b>TOTALS</b>	<b>2</b>	<b>2</b>	<b>1</b>

RIP RAP SCHEDULE		
STATION	FILTER FABRIC FOR USE WITH RIPRAP	STONE RIPRAP CLASS B3
142+39.00, 50' lt	61 sq yd	61 sq yd

END SECTION SCHEDULE EACH			
STATION	PRC FL- END SECTION - 12"	PRC FL- END SECTION - 24"	PRC FL- END SECTION - 24"
IL 57 - STA 142+25.00, 34' rt	1		
RADIO - STA 47+25.00, 42.1' rt			1
SIXTH - STA 9+00.00, CL		2	
<b>TOTALS</b>	<b>1</b>	<b>2</b>	<b>1</b>

PIPE CULVERT SCHEDULE- FOOT	
LOCATION	PC, TY 2 CS/AL PC, TY 2 CS/AL CULVERT PIPE - 18"
<b>ALONG RADIO ROAD</b>	
STA 41+54.44, 25.20' lt	48
STA 42+60.00, 28.00' lt	68
STA 44+59.97, 34.43' lt	84
<b>TOTALS</b>	<b>200</b>

SEEDING SCHEDULE - ACRE		
LOCATION	SEEDING CLASS, 2A	
	LEFT	RIGHT
<b>IL 57</b>		
135+25.00 - 149+00.00	0.23	0.17
70+00.00 - 83+00.00	0.08	0.11
<b>RADIO ROAD</b>		
37+25.00 - 40+00.00	0.08	0.09
40+00.00 - 49+79.00	0.21	0.28
<b>SIXTH STREET</b>		
6+75.00 - 8+75.00	0.04	0.04
<b>EIGHTH STREET</b>		
0+50.00 - 1+00.00		0.01
<b>SUBTOTAL</b>	<b>0.64</b>	<b>0.7</b>
<b>TOTAL</b>	<b>1.34</b>	

TEMPORARY SEEDING SCHEDULE		
LOCATION	TEMPORARY SEEDING (ACRES)	
	LEFT	RIGHT
STAGE I - IL 57 NORTH LEG		0.13
STAGE II - IL 57 SOUTH LEG		0.19
STAGE II - IL 57 NORTH LEG	0.14	
STAGE II - IL 57 SOUTH LEG	0.1	
STAGE II - RADIO ROAD	0.03	
STAGE III - IL 57 NORTH LEG		0.17
STAGE III - RADIO ROAD	0.05	0.15
<b>SUBTOTAL</b>	<b>0.32</b>	<b>0.64</b>
<b>TOTAL</b>	<b>0.96</b>	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF QUANTITIES

FAP 502 (IL 57) & RADIO ROAD  
SECTION (53RS-7, P(RS-2)) N, TS  
ADAMS COUNTY  
QUINCY, IL

SCALE: VERT.  
HORIZ.  
DATE 01-23-04

DRAWN BY TMJ  
CHECKED BY MEB

\*DCN-SPEC\*  
\*DATE-TIME\*  
\*REF 01