

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662		SANGAMON	18	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• D6 MEDIAN REPAIR 2005				

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

URBAN

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE - I000
				100% State
20201500	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	37	37
42000400	PORTLAND CEMENT CONCRETE PAVEMENT, 9"	SQ YD	32	32
44000100	PAVEMENT REMOVAL	SQ YD	17	17
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2191	2191
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ. FT	5377	5377
44200547	CLASS A PATCHES, TYPE IV, 9 INCH	SQ YD	78	78
44213000	PATCHING REINFORCEMENT	SQ YD	78	78
44213200	SAW CUTS	FOOT	56	56
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE I FRAME, OPEN LID	EACH	1	1
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	906	906
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	144	144

PLOT DATE = 2/07/2005
 FILE NAME = I:\2005\72950\SUMMARY.dgn
 PLOT SCALE = 100.000' / IN.
 REFERENCE = #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
 HORIZ.
 DATE

DRAWN BY BDK
 CHECKED BY JRK