

| | | | | |
|-------------------------|----------|------------------|--------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 662 | - | SANGAMON | 18 | 6 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |
| • 06 MEDIAN REPAIR 2005 | | | | |

LOCATION NO. 2 (IL 4 @ ILES AVE.)

| PAY CODE | ITEM | UNITS | QTY |
|----------|------------------------------------------------------------------------------------|-------|-----|
| 20201500 | SUB-BASE GRANULAR MATERIAL, TY B | TON | 7 |
| 42000400 | PCC PAVEMENT, 9" | SQ YD | 7 |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 17 |
| 44000500 | COMBINATION CURB & GUTTER REMOVAL | FOOT | 43 |
| 44002020 | CONCRETE MEDIAN SURFACE REMOVAL | SQ FT | 60 |
| 60608500 | COMBINATION CONCRETE CURB & GUTTER, TY M-6.06 | FOOT | 11 |
| 60610400 | COMBINATION CONCRETE CURB & GUTTER, TY M-6.24 | FOOT | 11 |
| 60610900 | COMBINATION CONCRETE CURB & GUTTER, TY M-6.24 (VAR WIDTH GUTTER) | FOOT | 17 |
| 60618300 | CONCRETE MEDIAN SURFACE, 4" | SQ FT | 64 |
| 81012600 | CONDUIT IN TRENCH, 2" DIA., PVC | FOOT | 7 |
| 81021550 | CONDUIT, AUGERED 2" DIA., PVC | FOOT | 38 |
| 87502700 | TRAFFIC SIGNAL POST, ALUMINUM 16 FT. | EACH | 1 |
| 87800100 | CONCRETE FOUNDATION, TYPE A | FOOT | 3 |
| 88200100 | TRAFFIC SIGNAL BACKPLATE | EACH | 1 |
| 89502350 | REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT | FOOT | 116 |
| 89502375 | REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT | EACH | 1 |
| X8801463 | SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-4 SECTION, 2-5 SECTION, BRACKET MOUNTED | EACH | 1 |

LOCATION NO. 1 (IL 4 @ BRUNS LN)

| PAY CODE | ITEM | UNITS | QTY |
|----------|---------------------------------------------------|-------|-----|
| 20201500 | SUB-BASE GRANULAR MATERIAL, TYPE B | TON | 20 |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 100 |
| 44002020 | CONCRETE MEDIAN SURFACE REMOVAL | SQ FT | 493 |
| 44200547 | CLASS A PATCHES, TYPE IV, 9 INCH | SQ YD | 78 |
| 44213200 | SAW CUTS | FOOT | 56 |
| 44213000 | PATCHING REINFORCEMENT | SQ YD | 78 |
| 60610400 | COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 | FOOT | 100 |
| 60618300 | CONCRETE MEDIAN SURFACE, 4 INCH | SQ FT | 493 |
| 88600100 | DETECTOR LOOP, TYPE I | FOOT | 104 |

PLOT DATE = 2/6/2005
 FILE NAME = \\s060908\shw\shw\shw\shw.dgn
 PLOT SCALE = 1/8"=1'-0"
 REFERENCE = #REF#

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY BDK
CHECKED BY

Rev.