

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71	(3RJ-1)	SANGAMON	10	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 72966

ITEM 63000000: STEEL PLATE BEAM GUARDRAIL, TYPE A	
LOCATION	FOOT
LT. STA. 109+92 TO LT. STA. 113+67	375
RT. STA. 109+04 TO RT. STA. 111+92	287.5
LT. STA. 116+90 TO LT. STA. 122+67	575
RT. STA. 124+22 TO RT. STA. 128+87	487.5
RT. STA. 140+12 TO RT. STA. 146+00	587.5
RT. STA. 151+62 TO RT. STA. 177+00	2587.5
LT. STA. 153+01 TO LT. STA. 174+26	2125
LT. STA. 245+00 TO LT. STA. 252+87.5	787.5
RT. STA. 248+00 TO RT. STA. 252+00	400
TOTAL =	8212.5

ITEM 63100045: TRAFFIC BARRIER TERMINAL, TYPE 2	
LOCATION	EACH
RT. STA. 124+00	1
RT. STA. 129+10	1
TOTAL =	2

ITEM 63100045: TRAFFIC BARRIER TERMINAL, TYPE 2	
LOCATION	EACH
RT. STA. 108+54.5 TO RT. STA. 109+04.5	1
RT. STA. 111+92 TO RT. STA. 112+42	1
RT. STA. 139+62.5 TO RT. STA. 140+12.5	1
RT. STA. 146+00 TO RT. STA. 146+50	1
RT. STA. 151+12.5 TO RT. STA. 151+62.5	1
LT. STA. 244+50 TO LT. STA. 245+00	1
RT. STA. 247+50 TO RT. STA. 248+00	1
RT. STA. 252+00 TO RT. STA. 252+50	1
TOTAL =	8

ITEM 6320031: GUARDRAIL REMOVAL	
LOCATION	FOOT
LT. STA. 112+63 TO LT. STA. 114+09 @ BRICKLER RD.	154
LT. STA. 114+51 TO LT. STA. 114+60	28
TOTAL =	182

ITEM 78200410: GUARDRAIL MARKERS, TYPE A	
MONO-DIRECT SILVER	EACH
(FOR ALL NEW GUARDRAIL)	
LOCATION	EACH
LT. STA. 109+92 TO LT. STA. 113+67	6
RT. STA. 109+04 TO RT. STA. 111+92	5
LT. STA. 116+90 TO LT. STA. 122+67	8
RT. STA. 124+22 TO RT. STA. 128+87	7
RT. STA. 140+12 TO RT. STA. 146+00	8
RT. STA. 151+62 TO RT. STA. 177+00	33
LT. STA. 153+01 TO LT. STA. 174+26	28
LT. STA. 245+00 TO LT. STA. 252+87.5	11
RT. STA. 248+00 TO RT. STA. 252+00	6
TOTAL =	112

ITEM 63301210: REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL, TYPE A		
LOCATION		FOOT
FROM	TO	
LT. STA. 114+60 TO LT. STA. 116+85	LT. STA. 114+65 TO LT. STA. 116+90	225
LT. STA. 122+67 TO LT. STA. 153+01	LT. STA. 122+67 TO LT. STA. 153+01	3037.5
LT. STA. 174+26 TO LT. STA. 176+13.5	LT. STA. 174+26 TO LT. STA. 176+13.5	187.5
TOTAL =		3450

ITEM X6330103: REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)		
LOCATION		EACH
FROM	TO	
LT. STA. 112+13 TO LT. STA. 112+63	LT. STA. 109+42 TO LT. STA. 109+92	1
LT. STA. 116+85 TO LT. STA. 117+35	RT. STA. 122+55 TO RT. STA. 123+05	1
LT. STA. 122+17 TO LT. STA. 122+67	RT. STA. 123+05 TO RT. STA. 123+55	1
LT. STA. 153+01 TO LT. STA. 153+51	LT. STA. 252+87.5 TO LT. STA. 253+37.5	1
LT. STA. 173+76 TO LT. STA. 174+26	RT. STA. 177+50 TO RT. STA. 178+00	1
LT. STA. 176+13.5 TO LT. STA. 176+63.5	LT. STA. 176+13.5 TO LT. STA. 176+63.5	1
LT BRICKLER RD. (LOCATION TO BE DETERMINED BY ENGINEER-SEE RADIUS GUARDRAIL DETAIL)		1
RT BRICKLER RD. (LOCATION TO BE DETERMINED BY ENGINEER-SEE RADIUS GUARDRAIL DETAIL)		1
TOTAL =		8

ITEM 78201000: TERMINAL MARKER-DIRECT APPLIED	
LOCATION	EACH
RT. STA. 108+54.5	1
RT. STA. 112+42	1
RT. STA. 139+62.5	1
RT. STA. 146+50	1
RT. STA. 151+12.5	1
LT. STA. 244+50	1
RT. STA. 247+50	1
RT. STA. 252+50	1
TOTAL =	8

ITEM X0322472: RADIUS GUARDRAIL		
LOCATION		EACH
LT. STA. 113+67 TO LT. STA. 114+06	L1	1
LT. STA. 114+51 TO LT. STA. 114+65	L2	1
RT. STA. 124+05 TO RT. STA. 124+22	L3	1
RT. STA. 128+87 TO RT. STA. 129+08	L4	1
TOTAL =		4

REVISIONS	
NAME	DATE
GUARDRAIL/TMJ	02-07-05

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 71 (IL 54)
 SECTION (3RJ-1)
 SANGAMON COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE 02-07-05

DRAWN BY TMJ
 CHECKED BY MEB

Rev.

c:\projects\ed52901\c9651705\cover.dgn
 2/7/2005
 *REF01