

teesleyck
2/7/2005
c:\projects\74049d\03004p.dgn

FAP SYL	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	(1Z,1Z)RS-2	CRAWFORD	18	3
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT NO.	

CONTRACT NO. 74049

80% F&D.
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		URBAN 1000		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3169	3169		
40600300	AGGREGATE (PRIME COAT)	TON	63	63		
40600990	TEMPORARY RAMP	SQ YD	34	34		
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	31688	31688		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	92	92		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3080	3080		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	528	528		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	18048	18048		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	840	840		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	303	303		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	59	59		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	513	513		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	528	528		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18048	18048		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	840	840		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	303	303		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	59	59		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	373	373		
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	2662	2662		

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY
OF
QUANTITIES**

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY