

teesleyck  
2/9/2005  
c:\projects\74069a\d05004pa.dgn  
GN& I

CONTRACT NO. 74069

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	*	WHITE		2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

\* D-7 BIT RESURF 2005-1

**GENERAL NOTES**

THE WORK INCLUDED IN SECTION D-7 BITUMINOUS RESURFACING 2005-1 CONSISTS OF 0.61 MILES OF BITUMINOUS SURFACE REMOVAL, RESURFACING WITH BITUMINOUS CONCRETE, BITUMINOUS SHOULDERS SUPERPAVE, PAVEMENT MARKING AND ANY OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

SHORT-TERM MARKINGS ON THE MILLED SURFACE SHALL BE PAINT.

ALL COLD MILLINGS FROM THIS PROJECT WILL BECOME PROPERTY OF THE STATE OF ILLINOIS. TWO WEEKS PRIOR TO ANY COLD MILLING ACTIVITY, PLEASE CONTACT BILL RANKIN OF THE ENFIELD MAINTENANCE YARD AT 611 N. FIRST ST. IN ENFIELD, IL (PHONE 618/963-2812) FOR SPECIFICS.

NO MAINLINE OR SHOULDER DROP-OFF EXCEEDING 1.5" WILL BE PERMITTED OVERNIGHT.

EXCAVATION FOR BITUMINOUS SHOULDERS, SUPERPAVE 6.5" SHALL BE INCLUDED IN THE COST OF THE PAY ITEM BITUMINOUS SHOULDERS, SUPERPAVE 6.5".

110 TONS OF AGGREGATE SHOULDERS, TYPE B HAS BEEN ADDED TO THE PROJECT TO CORRECT ANY EXISTING AGGREGATE SHOULDER DROP-OFFS. AGGREGATE SHOULDERS, TYPE B SHALL BE PLACED AS DIRECTED BY THE ENGINEER.

THE RESIDENT ENGINEER SHALL BE THE SOLE JUDGE CONCERNING THE CURING TIME FOR THE VARIOUS BITUMINOUS LIFTS.

THE CONTRACTOR SHALL PROVIDE INTERNET ACCESS TO THE BITUMINOUS PLANT QUALITY CONTROL LAB SO THAT BITUMINOUS PLANT REPORTS CAN BE E-MAILED TO THE DISTRICT HEADQUARTERS. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE UNIT PRICES FOR OTHER ITEMS IN THE CONTRACT.

BITUMINOUS MATERIALS (PRIME COAT) SHALL BE EITHER RC-70 OR SS-1HP.

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

APPLICATION	FRICION AGGREGATE	AC/PG	RAP%(MAX)	DESIGN AIR Voids	MIXTURE COMPOSITION
SURF. COURSE	MIX C	64-22	15	4.0% @ NDESIGN = 50	IL-9.5 OR IL-12.5
BIT. SHLDS.: FIRST LIFT	N/A	58-22	25	4.0% @ NDESIGN = 70	IL-19.0
BIT. SHLDS.: SECOND LIFT	N/A	58-22	25	4.0% @ NDESIGN = 30	IL-9.5

**INDEX OF SHEETS**

SHEET NO	TITLE
1	COVER SHEET
2	INDEX OF SHEETS, GENERAL NOTES
3	SUMMARY OF QUANTITIES
4-5	TYPICAL SECTIONS
6	SCHEDULES
7	PLAN SHEET

THE FOLLOWING STANDARDS ARE PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NUMBER 7:

000001-04	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
701006-02	OFF-ROAD OPERATIONS, 2L 2W, 15' TO 24" AWAY, FOR SPEEDS >= 45 MPH
701301-02	LANE CLOSURE, 2L 2W, SHORT TIME OPERATIONS
701306-01	LANE CLOSURE, 2L 2W, SLOW MOVING OPERATIONS, DAY ONLY FOR SPEEDS >= 45 MPH
701311-02	LANE CLOSURE, 2L 2W, MOVING OPERATIONS, DAY ONLY
701326-02	LANE CLOSURE, 2L 2W, PAVEMENT WIDENING, FOR SPEEDS >= 45 MPH
702001-05	TRAFFIC CONTROL DEVICES
780001-01	TYPICAL PAVEMENT MARKINGS

PLOT DATE = 2/9/2005  
FILE NAME = #FILEL4  
PLOT SCALE = #REF  
REFERENCE = #REF

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<b>GENERAL NOTES &amp; INDEX OF SHEETS</b>
SCALE:	VERT. DATE	HORIZ. CHECKED BY
		DRAWN BY