

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	*	WHITE		3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* D-7 BIT RESURF 2005-1				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	890	890		
40600300	AGGREGATE (PRIME COAT)	TON	20	20		
40600990	TEMPORARY RAMP	SQ YD	30	30		
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	8850	8850		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	110	110		
48202410	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2"	SQ YD	50	50		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	960	960		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	110	110		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	7440	7440		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	41	41		
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	750	750		

teasleyck  
 2/9/2005  
 ct\projects\74069d\05004pa.dgn  
 TYP

PLOT DATE \* 2/9/2005  
 FILE NAME \* #FILE#  
 PLOT SCALE \* #SCALE#  
 REFERENCE \* #REF#

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

SCALE: VERT. \_\_\_\_\_  
 DATE: \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_