

teesleyck  
2/9/2005  
c:\projects\74069d\05004pa.dgn  
TYP

CONTRACT NO. 74069

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	*	WHITE		6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

• D-7 BIT RESURF 2005-1

MARKING SCHEDULE

STATION TO STATION	LENGTH	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING - LINE 4"	RAISED REFLECTIVE PAVEMENT MARKERS
	LIN FT	FEET	SQ FT	FEET	EACH
214+40 TO 218+25	385	115	13	1251	5
218+25 TO 246+55	2830	845	96	6188	36
TOTALS		960	110	7440	41

PAVING SCHEDULE

STATION TO STATION	LENGTH	AVERAGE PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	TEMPORARY RAMP	BITUMINOUS SURFACE REMOVAL 1 1/2"	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2"	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50
	LIN FT	FEET	SQ YD	GAL	TON	SQ YD	SQ YD	TON	SQ YD	TON
214+40 TO 214+45	5	26	14	1	0.03	16	14	0.2		1
214+45 TO 235+85	2140	26	6182	620	13.7		6193	78.8		522
235+85 TO 236+85	100	24	267	27	0.6		267	3.8		23
236+85 TO 246+50	965	22	2359	236	5.2		2363	26.8	50	199
246+50 TO 246+55	5	22	12	1	0.03	14	12	0.2		1
LT 236+80 TO LT 238+30	150	3	50	5	0.1					4
TOTALS				890	20	30	8850	110	50	750

PLOT DATE = 2/9/2005  
FILE NAME = #FILE#  
PLOT SCALE = #SCALE#  
REFERENCE = #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT.  
DATE:           HORIZ.

DRAWN BY  
CHECKED BY