

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
785	132-3I, 133RS-5	MADISON	29	6
STA.		TO STA.		
CONTRACT NO.: 76796				

PAVING SCHEDULE

LOCATION	BITUMINOUS SURFACE REMOVAL, 2"	BITUMINOUS SURFACE REMOVAL, 2 1/2"	PAVED SHOULDER REMOVAL	BITUMINOUS MATERIALS, PRIME COAT	AGGREGATE PRIME COAT	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	STABILIZED SUB-BASE 4"	AGGREGATE BASE COURSE, TYPE B	PCC PAVEMENT, 10" (JOINTED)	STRIP REFLECTIVE CRACK CONTROL TREATMENT	BITUMINOUS SHOULDERS SUPERPAVE, 8"	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90 9"
STA TO STA	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	SQ YD	TON	SQ YD	FOOT	SQ YD	SQ YD
LOCATION 1													
IL 111/140													
94+14.7 TO 98+00.			591					665		576.1		393	
98+00. TO 99+41.9													
FOSTERBURG RD													
15+40.2 TO 18+00.			106	0.16	0.79		44				142		146
18+00. TO 20+00.	525.0												
ENTRANCE													
96+61. TO 97+8.7				0.88	1.42		48		95				
LOCATION 2													
497+21. TO 500+00.		1050		0.66	3.16	58.8	88.2						
500+00. TO 502+30.		887		0.56	2.66	49.7	74.5						
TOTAL	525	1937	697	2.2	8.0	109	255	665	95	576.1	142	393	146

PAVEMENT MARKING SCHEDULE

LOCATION	PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING										POLYUREA PAVEMENT MARKING			RAISED REFLECTIVE PAVEMENT MARKERS					
		LINES										LETTERS & SYMBOLS		LINE			REMOVAL	ONE WAY CRYSTAL	ONE WAY AMBER	TWO WAY AMBER
		4"		8"	12"			24"	LEFT TURN ARROW	COMB LEFT TURN/THRU ARROW	4"									
STA TO STA	SQ FT	SOLID WHITE EDGE LINE	SOLID WHITE LANE LINE	SOLID DOUBLE YELLOW LINE	SOLID WHITE LINE	SOLID WHITE CROSSWALK	SOLID YELLOW DIAGONAL	SOLID WHITE CHEVRON			STOP BAR	SQ YD	SQ YD	SOLID WHITE EDGE LINE	SOLID WHITE LANE LINE	SOLID WHITE SKIP DASH	EACH	EACH	EACH	EACH
LOCATION 1																				
IL 111/140																				
94+14.7 TO 98+00.	176.6											388.1		40.0	8.0	8.0				
98+00. TO 99+41.9												143.0	142.6							
FOSTERBURG RD																				
15+40.2 TO 18+00.	228.6		259.8					125.8		31.2	52.0				21.0	21.0				
18+00. TO 20+00.		133.4	157.2						14.8	15.6	26.0									
LOCATION 2																				
497+21.1 TO 500+00.		313.8	120.0	745.0		83.0	53.0		25.0	31.2					18.0	4.0	8.0	6.0		
500+00. TO 502+30.		94.0	45.0	606.4		106.0	54.0		33.0	31.2					13.0	2.0	6.0	5.0		
SUB-TOTAL	405.2	541.2	582.0	1351.4		189.0	107.0	125.8	72.8	109.2	78.0	531.1	142.6	40.0	60.0	35.0	14.0	11.0		
TOTAL	405.2		2475			422		73	187			714			60		60			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**MISCELLANEOUS SCHEDULES**  
**LOCATIONS 1 & 2**  
 FAP ROUTE 785  
 SECTION 132-3I, 133RS-5  
 MADISON COUNTY  
 DRAWN BY:

PLAN  
 SURVEYED BY  
 PLOTTED BY  
 CHECKED BY  
 DATE