

SPECIALTY ITEMS	CODED PAY ITEM	ITEM DESCRIPTION	UNIT	QUANTITIES			
				CONSTRUCTION TYPE CODE			TOTAL
				1000-2A	Y031-1F	X071-2A	
*	20100110	TREE REMOVAL (6 TO 15 INCHES DIAMETER)	UNIT	38	0	0	38
*	20100210	TREE REMOVAL (OVER 15 INCHES DIAMETER)	UNIT	58	0	0	58
	20200100	EARTH EXCAVATION	CU YD	268	0	0	268
*	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	223	0	0	223
	20300100	CHANNEL EXCAVATION	CU YD	0	0	898	898
	20400800	FURNISHED EXCAVATION	CU YD	431	0	0	431
	20700220	POROUS GRANULAR EMBANKMENT	CU YD	0	0	189	189
B	* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1829	0	0	1829
B	* 25000210	SEEDING, CLASS 2A	ACRE	0.07	0	0	0
B	* 25000300	SEEDING, CLASS 3	ACRE	0.27	0	0	0
B	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	34	0	0	34
B	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	34	0	0	34
B	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	34	0	0	34
B	25100120	MULCH METHOD 2	TON	0.14	0	0	0
*	25100640	EROSION CONTROL FABRIC	SQ YD	1262	0	0	1262
B	25200200	SUPPLEMENTAL WATERING	UNIT	11	0	0	11
*	28000300	TEMPORARY DITCH CHECK	EACH	5	0	0	5
*	28000400	PERIMETER EROSION BARRIER	FOOT	1142	0	0	1142
	28100107	STONE RIPRAP CLASS A4	SQ YD	0	0	506	506
	28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	0	0	527	527
	28400100	GABIONS	CU YD	0	0	21	21
*	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLONS	1640	0	0	1640
	42001165	BRIDGE APPROACH PAVEMENT	SQ YD	302	0	0	302
*	44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	413	0	0	413
*	44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	3	0	0	3
*	44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	4	0	0	4
*	44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	10	0	0	10
*	44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	7	0	0	7
	44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	558	0	0	558
*	48100100	AGGREGATE SHOULDERS, TYPE A	TON	55	0	0	55
*	48200400	BITUMINOUS SHOULDERS, 6"	SQ YD	799	0	0	799
*	50100100	REMOVAL OF EXISTING STRUCTURE	EACH	0	0	1	1
	50200100	STRUCTURE EXCAVATION	CU YD	0	0	225	225
	50300225	CONCRETE STRUCTURES	CU YD	0	0	36	36
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	0	0	113	113
	50300260	BRIDGE DECK GROOVING	SQ YD	0	0	325	325
	50300275	CONCRETE HANDRAIL	CU YD	0	0	16	16
*	50300300	PROTECTIVE COAT	SQ YD	0	0	419	419
	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	LUMP SUM	0	0	1	1
	50500505	STUD SHEAR CONNECTORS	EACH	0	0	1134	1134
	50800205	REINFORCEMENT BARS EPOXY COATED	POUND	0	0	28690	28690
	51201600	FURNISHING STEEL PILES - HP12X53	FOOT	0	0	864	864
	51202700	DRIVING STEEL PILES	FOOT	0	0	864	864
	51203600	TEST PILES STEEL - HP12X53	EACH	0	0	2	2
*	51205200	TEMPORARY SHEET PILING	SQ FT	0	0	1578	1578
	51500100	NAME PLATES	EACH	0	0	1	1

SPECIALTY ITEMS	CODED PAY ITEM	ITEM DESCRIPTION	UNIT	QUANTITIES			
				CONSTRUCTION TYPE CODE			TOTAL
				1000-2A	Y031-1F	X071-2A	
	54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE, 15"	FOOT	27	0	0	27
	54213867	STEEL END SECTIONS, 12"	EACH	2	0	0	2
	54213870	STEEL END SECTIONS, 15"	EACH	2	0	0	2
	60103500	PIPE DRAINS, CORRUGATED STEEL 12"	FOOT	35	0	0	35
	60900315	TYPE D INLET BOX, STANDARD 609006	EACH	2	0	0	2
	60900515	CONCRETE THRUST BLOCKS	EACH	2	0	0	2
	63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	405	0	0	405
	63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	4	0	0	4
	63200310	GUARDRAIL REMOVAL	FOOT	456	0	0	456
	66410410	CHAIN LINK FENCE TO BE RELOCATED	FOOT	184	0	0	184
	70101700	TRAFFIC CONTROL AND PROTECTION	LUMP SUM	1	0	0	1
B	* 70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	0	4	0	4
B	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	124	0	0	124
B	70300625	TEMPORARY PAINT PAVEMENT MARKING LINE, 4"	FOOT	2476	0	0	2476
B	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2600	0	0	2600
B	* 70400100	TEMPORARY CONCRETE BARRIER	FOOT	414	0	0	414
B	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	414	0	0	414
B	78000200	THERMOPLASTIC PAVEMENT MARKING LINE- 4"	FOOT	964	0	0	964
B	* 78000300	THERMOPLASTIC PAVEMENT MARKING LINE- 5"	FOOT	964	0	0	964
B	* 78001110	PAINT PAVEMENT MARKING LINE- 4"	FOOT	274	0	0	274
B	* 78001120	PAINT PAVEMENT MARKING LINE- 5"	FOOT	274	0	0	274
*	78200400	GUARDRAIL REFLECTORS	EACH	17	0	0	17
B	* A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	3	0	0	3
B	* A2004216	TREE, FRAXINUS PENNSYLVANICA SUMMIT (SUMMIT GREEN ASH), 2" CALIPER, BALLED AND BURLAPPED	EACH	3	0	0	3
	* X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	174	0	0	174
	* X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL 19.0L, N70	TON	741	0	0	741
	* X4066770	LEVELING BINDER (MACHINE METHOD) SUPERPAVE, N70	TON	20	0	0	20
	* X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	CAL MO.	8	0	0	8
	* X7015050	PORTABLE CHANGEABLE MESSAGE SIGN	CAL MO.	8	0	0	8
*	* XX001302	ENERGY DISSIPATOR (SPECIAL)	EACH	4	0	0	4
	* Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	7	0	0	7
	* Z0002600	BAR SPLICERS	EACH	0	0	333	333
	* Z0013798	CONSTRUCTION LAYOUT	LUMP SUM	1	0	0	1
	* XX001328	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL)	EACH	4	0	0	4

SHEET	INDEX OF SCHEDULES
SCH-1	1 SCHEDULE OF EARTH EXCAVATION/EMBANKMENT QUANTITIES
SCH-1	2 SCHEDULE OF SEEDING AND RELATED ITEMS
SCH-1	3 SCHEDULE OF PAVEMENT MATERIALS
SCH-1	4 SCHEDULE OF TOPSOIL STRIPPING
SCH-1	5 SCHEDULE OF TREES
SCH-1	6 SCHEDULE OF GUARDRAIL AND RELATED ITEMS
SCH-1	7 SCHEDULE OF SEWER PIPING
SCH-1	8 SCHEDULE OF PAVEMENT MARKINGS
SCH-1	9 SCHEDULE OF REMOVAL ITEMS
SCH-1	10 SCHEDULE OF EROSION CONTROL MEASURES

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
MCCLURE ENGINEERING	02/03/05	SUMMARY OF QUANTITIES SCALE: VERT. N.T.S. HORIZ. N.T.S. DATE _____ DRAWN BY AJP CHECKED BY CRF

* Revised 4/14/05