


CODENO.	SUMMARY OF QUANTITIES		CONSTRUCTION TYPE CODE	
	ITEM	UNITS	TOTAL	I000-2A
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	84	84
20200100	EARTH EXCAVATION	CU. YD.	617	617
20400800	FURNISHED EXCAVATION	CU. YD.	142	142
* 20800150	TRENCH BACKFILL	CU. YD.	110	110
25000100	SEEDING, CLASS 1	ACRE	1.2	1.2
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	110	110
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	110	110
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	110	110
25100105	MULCH, METHOD 1	ACRE	1.2	1.2
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	122	122
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	717	717
* 35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ. YD.	841	841
* 35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ. YD.	102	102
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1083	1083
40600300	AGGREGATE (PRIME COAT)	TON	27	27
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ. YD.	743	743
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ. YD.	97	97
40600990	TEMPORARY RAMP	SQ. YD.	352	352
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ. YD.	26	26
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ. YD.	884	884
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ. FT.	23,840	23,840
* 44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ. YD.	9456	9456
* 44000100	PAVEMENT REMOVAL	SQ. YD.	1513	1513
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ. YD.	691	691
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5960	5960
44000600	SIDEWALK REMOVAL	SQ. FT.	8513	8513
44003100	MEDIAN REMOVAL	SQ. FT.	230	230

* SEE SPECIAL PROVISIONS

DRAWN BY J.J.S.		SUMMARY OF QUANTITIES EAST GRANT STREET IMPROVEMENTS	
CHECKED BY L.L.Q.			
APPROVED BY W.J.S.		MACOMB, ILLINOIS  Consulting Engineers / Land Surveyors 1970 West Lafayette Avenue Jacksonville, Illinois 62650 Phone : 217-245-4146 Fax : 217-245-4149 IL Design Firm Registration No. 184-000852.	
DATE JANUARY, 2005			
REVISIONS			
DATE	BY		
3/7/05	M.G.M.		
FIELD BOOK:	SCALE:	JOB NO. 04e1486	SHEET 3 OF 66