

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
749	122RS-3	*	54	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* DOUGLAS, COLES & EDGAR CONTRACT NO. 90769				

LOCATION OF WORK: FAP 749 (IL ROUTE 133)
SECTION 122RS-3
DOUGLAS, COLES, EDGAR COUNTY

	EDGAR		
	FAP ROUTE 749 (IL 133) DOUGLAS COUNTY STA 550+20.6 TO STA 709+94.5 BK 80% FED 20% STATE 1000	FAP ROUTE 749 (IL 133) COLES COUNTY STA 710+00.00 TO STA 991+50.5 80% FED 20% STATE 1000	FAP ROUTE 749 (IL 133) EDGAR COUNTY STA 991+50.5 TO STA 1080+50 80% FED 20% STATE 1000
	FAP ROUTE 749 (IL 133) IL RTE. 49 STA 31+19 TO STA 59+50.66 80% FED 20% STATE 1000-1A		

CONSTRUCTION TYPE CODE:

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	16,764	4,611	8,058	2,571	1524.0
40600300	AGGREGATE (PRIME COAT)	TON	338	93	162	52	31.0
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	844.0	87.0	496.0	87.0	174.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	103.0	0.0	103.0	0.0	0.0
40600990	TEMPORARY RAMP	SQ YD	154.0	14.0	98.0	14.0	28.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	425.0	81.0	278.0	59.0	7.0
40800030	AGGREGATE (PRIME COAT)	TON	10.0	2.0	6.0	1.0	1.0
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	357.5	68.5	233.9	49.7	5.4
44000003	BITUMINOUS SURFACE REMOVAL 3/4"	SQ YD	162,093	46,147	73,023	27,685	15238
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	9,402.0	0.0	6175.0	1181.0	2046.0
44000025	BITUMINOUS SURFACE REMOVAL (SPECIAL)	SQ YD	2,173.0	434.0	1357.0	318.0	64.0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	26.0	0.0	26.0	0.0	0.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4,343.0	1290.0	2149.0	904.0	0.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	1	3.0	2	0.0
67100100	MOBILIZATION	L SUM	1.0	0.1	0.8	0.1	0.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.1	0.8	0.1	0.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	0.1	0.8	0.1	0.0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	0.0	1.0	0.0	0.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	27,122.0	6390	14983.2	4024.0	1724.8
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SO FT	310.0	0.0	122.0	94.0	94.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	150,310.0	36852.0	69339.0	30607.0	13512.0
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	750.0	0.0	0.0	361.0	389.0
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,148.0	0.0	0.0	1104.0	1044.0
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	176.0	0.0	72.0	52.0	52.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2,260.0	532.0	1249.0	335.0	144.0

REVISIED 4/15/05

SUMMARY OF QUANTITIES (CONTD.)

F.A.P. RYE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
749	122RS-3	*	54	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* DOUGLAS, COLES & EDGAR				
CONTRACT NO. 5076S				

LOCATION OF WORK: FAP 749 (IL ROUTE 133)
SECTION 122RS-3
DOUGLAS, COLES, EDGAR COUNTY

EDGAR

FAP ROUTE 749 (IL 133) DOUGLAS COUNTY STA 550+20.6 TO STA 709+94.5 BK	FAP ROUTE 749 (IL 133) COLES COUNTY STA 710+00.00 TO STA 991+50.5	FAP ROUTE 749 (IL 133) EDGAR COUNTY STA 991+50.5 TO STA 1080+50	FAP ROUTE 749 (IL 133) IL RTE. 49 STA 31+19 TO STA 59+50.66
80% FED 20% STATE 1000	80% FED 20% STATE 1000	80% FED 20% STATE 1000	80% FED 20% STATE 1000-1A

CONSTRUCTION TYPE CODE:

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	310.0	0.0	122.0	94.0	94.0
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21,728.0	0.0	0.0	10829.0	10899.0
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	750.0	0.0	0.0	389.0	361.0
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,148.0	0.0	0.0	1104.0	1044.0
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	104.0	0.0	0.0	52.0	52.0
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	128,582.0	36852.0	69339.0	19778.0	2613.0
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	811.0	200.0	343.0	167.0	101.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	781.0	200.0	341.0	164.0	76.0
△ X4032500	BITUMINOUS MATERIALS COVER & SEAL COAT SPECIAL	GALLON	603	60.3	422.1	120.6	0.0
X4040100	SEAL COAT AGGREGATE SPECIAL	TON	30.0	3.0	21.0	6.0	0.0
△ X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	14,302	3,877	6,720	2,425	1280.0
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	6,700	1,936	3,069	1,163	532.0
X4401705	PARTIAL DEPTH REMOVAL	SQ YD	1,683.0	775.0	701.0	161.0	46.0
Z0004800	BITUMINOUS MIXTURE FOR PATCHING	TON	835.0	379.0	337.0	79.0	40.0
Z0010900	COLD MILLING (SPECIAL)	FOOT	1,022.0	0.0	1022.0	0.0	0.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	0.0	1.0	0.0	0.0

• SPECIALTY ITEMS

△ REVISED 4/15/05