

## SCHEDULES OF QUANTITIES

F.A.P. SECTION COUNTY TOTAL SHEET	RTE. 122R5-3 * 54 20
STA. TO STA.	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	
* DOUGLAS, COLES & EDGAR CONTRACT NO. 90769	

### 40800040 INCIDENTAL BITUMINOUS SURFACING (CONTD)

STATION	AREA (SQ. YDS.)	MAILBOX (TONS)	FIELD ENTR. (TONS)	PRIV ENT. W/ MBTO (TONS)	PRIVATE ENTR. (TONS)	COMMER. ENTR. (TONS)	SIDEROAD (TONS)
<b>EDGAR COUNTY</b>							
(TR 2800 E/000 E) 991+50.5 LT	81						6.8
F.E. 1000+23 RT	14		1.2				
F.E. 1003+30 RT	14		1.2				
F.E. 1003+76 LT	14		1.2				
F.E. 1005+03 RT	14		1.2				
F.E. 1006+18 RT	14		1.2				
F.E. 1013+68 RT	14		1.2				
F.E. 1018+79 LT	14		1.2				
F.E. 1019+41 LT	14		1.2				
F.E. 1026+13 LT	14		1.2				
F.E. 1034+06 LT	14		1.2				
F.E. 1034+41 LT	14		1.2				
F.E. 1034+41 RT	14		1.2				
F.E. 1035+45 RT	14		1.2				
(TR 100 E) 1046+45 RT	85						7.1
(TR 100 E) 1046+46 LT	88						7.4
F.E. 1051+42 RT	14		1.2				
MBTO 1053+67 LT	34	2.9					
F.E. 1059+16 RT	14		1.2				
F.E. 1060+11 LT	14		1.2				
F.E. 1068+08 LT	14		1.2				
C.E. 1071+78 LT	65					5.5	
<b>SUBTOTAL =</b>	<b>591</b>	<b>2.9</b>	<b>20.4</b>	<b>0.0</b>	<b>0.0</b>	<b>5.5</b>	<b>21.3</b>

### 40800040 INCIDENTAL BITUMINOUS SURFACING (CONTD)

STATION	AREA (SQ. YDS.)	MAILBOX (TONS)	FIELD ENTR. (TONS)	PRIV ENT. W/ MBTO (TONS)	PRIVATE ENTR. (TONS)	COMMER. ENTR. (TONS)	SIDEROAD (TONS)
<b>ROUTE 49</b>							
C.E. 46+84 LT	64					5.4	
<b>SUBTOTAL =</b>	<b>64</b>	<b>0.0</b>	<b>0.0</b>	<b>0.0</b>	<b>0.0</b>	<b>5.4</b>	<b>0.0</b>
<b>TOTAL QUANTITY =</b>	<b>4246</b>	<b>6.2</b>	<b>76.8</b>	<b>0.0</b>	<b>92.5</b>	<b>33.5</b>	<b>139.9</b>

### 44000006 BITUMINOUS SURFACE REMOVAL-1 1/2"

STATION TO STATION	SQ. YDS.
<b>COLES COUNTY</b>	
811+00 829+52.3	6175
<b>SUB-TOTAL =</b>	<b>6175 SQ. YDS.</b>
<b>EDGAR COUNTY</b>	
1072+14 1075+15	1181
<b>SUB-TOTAL =</b>	<b>1181 SQ. YDS.</b>
<b>IL RTE. 49</b>	
43+55 44+70	1024
45+32.53 46+54	1022
<b>SUB-TOTAL =</b>	<b>2046 SQ. YDS.</b>
<b>TOTAL =</b>	<b>9402 SQ. YDS.</b>

### 44000025 BITUMINOUS SURFACE REMOVAL (SPECIAL)

STATION	AREA (SQ. YDS.)
<b>DOUGLAS COUNTY</b>	
(P.E. W/MBTO) 685+16.5 LT	63
(TR 1925 E) 567+40 LT	63
(TR 1975 E) 598+00 RT	71
(TR 2100 E) 671+51.5 LT	45
(TR 2100 E) 671+62.5 LT	45
(TR 2175 E) 709+20 RT	104
(TR 2150 E) 698+58.5 LT	43
<b>SUBTOTAL =</b>	<b>434 SQ. YDS.</b>
<b>COLES COUNTY</b>	
P.E. 746+14.5 RT	43
P.E. 750+74 RT	43
(TR 2300 E) 764+46 RT	97
(MAIN ST.) 778+59 LT	86
C.E. 784+17 RT	43
(TR 2500 E) 846+01 LT	50
(TR 2500 E) 846+21 RT	81
(TR 2600 E) 884+45 RT	81
(TR 2680 E) 927+54 LT	106
(TR 2700 E) 938+17 RT	111
(SIDEROAD) 951+60 LT	81
P.E. 953+08 RT	85
P.E. 953+74 RT	39
(TR 2780 E) 978+29 RT	81
C.E. 805+32 RT	43
P.E. 809+14 RT	43
C.E. 832+21 RT	39
(TEETER ST.) 832+45 RT	86
(TEETER ST.) 832+52.5 LT	119
<b>SUBTOTAL =</b>	<b>1357 SQ. YDS.</b>

### EDGAR COUNTY

(TR 2800 E/000 E) 991+50.5 LT	81
(TR 100 E) 1046+45 RT	85
(TR 100 E) 1046+46 LT	88
C.E. 1071+78 LT	64
<b>SUBTOTAL =</b>	<b>318 SQ. YDS.</b>
<b>ROUTE 49</b>	
C.E. 46+84 LT	64
<b>SUBTOTAL =</b>	<b>64 SQ. YDS.</b>
<b>TOTAL QUANTITY =</b>	<b>2173 SQ. YDS.</b>

### 44201803 CLASS D PATCHES, TYPE II, 13 INCH

STATION	DIRECTION	LANE	LENGTH (FT)	WIDTH (FT)	DEPTH (IN)	PATCH AREA TYPE II (SQ YD)
<b>COLES COUNTY</b>						
710+06	WB	DRIVE	5	13	13	7.2
710+06	EB	DRIVE	5	13	13	7.2
715+25	WB	DRIVE	4	13	13	5.8
715+25	EB	DRIVE	4	13	13	5.8
<b>TOTAL =</b>						<b>26.0 SQ YD</b>