

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
749	I22R5-3	*	54	21
STA. TO STA.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
* DOUGLAS, COLES & EDGAR				
CONTRACT NO. 90769				

SCHEDULES OF QUANTITIES

78000100 THERMOPLASTIC PAVEMENT MARKING-LTRS. & SYMB.

STATION	SO. FT.
<u>IL RTE. 49</u>	
43+00 (LT. ARROW)	15.6
43+66 (LT. ARROW)	15.6
44+32 (LT. ARROW)	15.6
45+73 (LT. ARROW)	15.6
46+41.50 (LT. ARROW)	15.6
47+10 (LT. ARROW)	15.6
SUB-TOTAL =	94.0 SQ. FT.
<u>EDGAR COUNTY</u>	
1071+50 (LT. ARROW)	15.6
1072+16 (LT. ARROW)	15.6
1073+04 (LT. ARROW)	15.6
1074+18 (LT. ARROW)	15.6
1074+84 (LT. ARROW)	15.6
1075+50 (LT. ARROW)	15.6
SUB-TOTAL =	94.0 SQ. FT.

STATION	SO. FT.
<u>COLES COUNTY</u>	
823+30.6 LT. "X"	54.0
832+30.6 LT. "R"	3.6
832+30.6 LT. "R"	3.6
826+48.2 RT. "X"	54.0
826+48.2 RT. "R"	3.6
826+48.2 RT. "R"	3.6
SUB-TOTAL =	122.0 SQ. FT.
TOTAL =	310.0 SQ. FT.

78000200 THERMOPLASTIC PAVEMENT MARKING-LINE 4" (WHITE)

STATION	TO	STATION	LIN. FT.
<u>EDGAR CO.</u>			
TURN LANE 1071+50		1073+50	180
TURN LANE 1075+50		1073+93	157
LT 1065+70		LT 1072+70	1400
RT 1065+70		RT 1072+90	1440
RT 1074+35		RT 1081+30	1390
LT 1074+50		LT 1081+30	1360
SUB-TOTAL =			5927 LIN. FT.
<u>IL RTE. 49</u>			
TURN LANE 43+00		44+62	162
TURN LANE 45+43		47+10	167
RT 37+20		RT 44+25	1410
LT 37+20		LT 44+30	1420
LT 45+65		LT 52+90	1450
RT 45+80		RT 52+90	1420
SUB-TOTAL =			6029 LIN. FT.
TOTAL =			11956 LIN. FT.

78000200 THERMOPLASTIC PAVEMENT MARKING-LINE 4" (DOUBLE YELLOW)

STATION	TO	STATION	LIN. FT.
<u>EDGAR CO.</u>			
1060+70		1073+00	2480
1074+00		1086+30	2422
SUB-TOTAL =			4902 LIN. FT.
<u>IL RTE. 49</u>			
45+60		552+90	2430
32+20		44+62	2440
SUB-TOTAL =			4870 LIN. FT.
TOTAL =			9772 LIN. FT.

78000400 THERMOPLASTIC PAVEMENT MARKING-LINE 6" (WHITE)

STATION	LIN. FT.
<u>IL RTE. 49</u>	
44+62	186
45+43	175
SUB-TOTAL =	361 LIN. FT.
<u>EDGAR CO.</u>	
1073+30	191
1073+93	198
SUB-TOTAL =	389 LIN. FT.
TOTAL =	750 LIN. FT.

78000600 THERMOPLASTIC PAVEMENT MARKING-LINE 12" (WHITE)

STATION	TO	STATION	LIN. FT.
<u>EDGAR CO.</u>			
RT 1065+70		RT 1072+82	175
LT 1065+70		LT 1072+80	188
RT 1074+28		RT 1081+30	166
LT 1074+20		LT 1081+30	188
MED. ISLANDS RT 1073+30			101
MED. ISLANDS LT 1073+93			102
SUB-TOTAL =			920 LIN. FT.
<u>IL RTE. 49</u>			
RT 37+20		RT 44+18	154
LT 37+20		LT 44+32	177
LT 45+83		LT 52+90	153
RT 45+70		RT 52+90	189
MED. ISLANDS RT 44+62			93
MED. ISLANDS LT 45+43			94
SUB-TOTAL =			860 LIN. FT.
TOTAL =			1780 LIN. FT.

78000600 THERMOPLASTIC PAVEMENT MARKING-LINE 12" (YELLOW)

STATION	TO	STATION	LIN. FT.
<u>EDGAR CO.</u>			
1065+70		1071+12	92
1075+88		1081+30	92
SUB-TOTAL =			184 LIN. FT.
<u>IL RTE. 49</u>			
37+20		42+62	92
47+48		52+90	92
SUB-TOTAL =			184 LIN. FT.
TOTAL =			368 LIN. FT.

78000650 THERMOPLASTIC PAVEMENT MARKING-LINE 24" (WHITE)

STATION	LIN. FT.
<u>EDGAR CO.</u>	
1073+00	12
1073+50	14
1073+93	14
1074+00	12
SUB-TOTAL =	52 LIN. FT.
<u>IL RTE. 49</u>	
44+50	12
44+62	14
45+43	14
45+60	12
SUB-TOTAL =	52 LIN. FT.
TOTAL =	104 LIN. FT.

78100100 RAISED REFLECTIVE MARKER (AMBER MONODIRECTIONAL) (40' CTS)

STATION	TO	STATION	EACH
<u>EDGAR COUNTY</u>			
1067+00		1071+00	20
1076+00		1080+00	20
SUB-TOTAL =			40 EACH
<u>IL RTE. 49</u>			
37+00		43+00	30
47+25		53+00	29
SUB-TOTAL =			59 EACH
TOTAL =			99 EACH