

SUMMARY OF QUANTITIES (CONT'D)

• 58-62,58-62-1,58-63)RS
CONTRACT NO. 90879

| | | | |
|--------|-------|-----|-------------|
| 72 | MACON | 135 | B |
| COUNTY | | | TOTAL SHEET |

SECTION NO. 90879

| LOCATION OF WORK: FAI ROUTE 72 (1-12) | | | | SECTION (58-62, 58-62-1, 58-63)RS | | | | MACON COUNTY | | | |
|---------------------------------------|--------|--------|--------|-----------------------------------|--------|--------|--------|----------------------------|--------|--------|--------|
| FAI-72 | FAI-72 | FAI-72 | FAI-72 | FAI-72 | FAI-72 | FAI-72 | FAI-72 | FAI-72 | FAI-72 | FAI-72 | FAI-72 |
| Sto 415+07.22 to 468+58.30 | | | | Sto 468+58.30 to 498+58.30 | | | | Sto 468+58.30 to 498+58.30 | | | |
| Macon County | | | | Macon County | | | | Macon County | | | |
| Urban | | | | Urban | | | | Urban | | | |
| 90% FED | | | | 90% FED | | | | 90% FED | | | |
| 1000 | | | | 1000 | | | | 1000 | | | |
| SFTY-3N | | | | SFTY-2A | | | | SFTY-2A | | | |
| 10% STATE | | | | 10% STATE | | | | 10% STATE | | | |
| 1000 | | | | 1000 | | | | 1000 | | | |
| CONSTRUCTION TYPE CODE: | | | | CONSTRUCTION TYPE CODE: | | | | CONSTRUCTION TYPE CODE: | | | |
| TOTAL QUANTITY | | | | TOTAL QUANTITY | | | | TOTAL QUANTITY | | | |

| | | | | | | | | | | |
|----------|--|-------|----------|---------|----------|-----|------|-----|-----|--------|
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 32310.0 | 3660.0 | 28650.0 | 0.0 | 0.0 | 0.0 | 0.0 | 8474.0 |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 110.0 | 0.0 | 110.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 160102.0 | 16873.0 | 143229.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 327.0 | 0.0 | 327.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 70300250 | TEMPORARY PAVEMENT MARKING - LINE 8" | FOOT | 3322.0 | 0.0 | 3322.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 215.0 | 0.0 | 215.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 72.0 | 0.0 | 72.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 70300625 | TEMPORARY PAINT PAVEMENT MARKING LINE 4" | FOOT | 52354.0 | 0.0 | 52354.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 6798.0 | 610.0 | 6188.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 3375.0 | 0.0 | 3375.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 3262.5 | 0.0 | 3262.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78003110 | PERFORMED PLASTIC PAVEMENT MARKING, TYPE 8 - LINE 4" | FOOT | 27187.0 | 2677.0 | 24510.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78005110 | EPOXY PAVEMENT MARKING - LINE 4" | FOOT | 4462.0 | 0.0 | 4462.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78008300 | POLYUREA PAVEMENT MARKING TYPE II- LETTERS & SYMBOLS | SQ FT | 110.0 | 0.0 | 110.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78008310 | POLYUREA PAVEMENT MARKING TYPE II- LINE 4" | FOOT | 160102.0 | 16873.0 | 143229.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78008330 | POLYUREA PAVEMENT MARKING TYPE II- LINE 6" | FOOT | 327.0 | 0.0 | 327.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78008340 | POLYUREA PAVEMENT MARKING TYPE II- LINE 8" | FOOT | 3322.0 | 0.0 | 3322.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78008350 | POLYUREA PAVEMENT MARKING TYPE II- LINE 12" | FOOT | 215.0 | 0.0 | 215.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78008370 | POLYUREA PAVEMENT MARKING TYPE II- LINE 24" | FOOT | 72.0 | 0.0 | 72.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 2255.0 | 268.0 | 1987.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78100105 | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | EACH | 48.0 | 0.0 | 48.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78200405 | GUARDRAIL MARKERS | EACH | 172.0 | 15.0 | 156.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 40.0 | 4.0 | 36.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 31815.0 | 0.0 | 31815.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 1648.0 | 134.0 | 1534.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78302897 | POLYMER CONCRETE | CU FT | 18.2 | 0.0 | 18.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78321468 | PLUG EXISTING DECK DRAINS | EACH | 18.0 | 0.0 | 18.0 | 0.0 | 18.0 | 0.0 | 0.0 | 0.0 |
| X0321744 | SILICONE JOINT SEALER, 2" | FOOT | 263.0 | 0.0 | 263.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| X0321962 | CONNECTION OF EXISTING PIPE UNDERDRAIN | EACH | 2.0 | 0.0 | 2.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |

REVISIONS

4-15-05