

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
716	130(R,R-URS)	MACON	36	5

CONTRACT NO. 90929

LOCATION OF WORK:

 URBAN
 STA. 57+07.00
 TO STA. 157+37.70
 80% FED.
 20% STATE

CONSTRUCTION TYPE CODE:

 I000
 TOTAL
 QUANTITY

CODE NO	ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13,166.0
40600300	AGGREGATE (PRIME COAT)	TON	265.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	2553.0
40600990	TEMPORARY RAMP	SQ YD	344.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	409.0
40800030	AGGREGATE (PRIME COAT)	TON	0.0
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	326.0
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	50.0
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	63,005.0
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	796.0
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	12.0
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	32.0
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	54.0
60255500	MANHOLES TO BE ADJUSTED	EACH	15.0
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	5.0
60266600	VALVE BOXES TO BE ADJUSTED	EACH	18.0
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	144.0
60401810	GRATES, TYPE 3	EACH	44.0
60622354	CONCRETE MEDIAN, TYPE SM-6 (DOWELLED)	SQ FT	312.0
60624610	CORRUGATED MEDIAN (DOWELLED)	SQ FT	10,752.0
60625900	P. C. C. RAMPED MEDIAN TERMINAL	EACH	14.0

REV 1