

**SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
716	130(R,R-1)RS	MACON	36	6

CONTRACT NO. 90929

LOCATION OF WORK:

URBAN  
 STA. 57+07.00  
 TO STA. 157+37.70  
 80% FED.  
 20% STATE

CONSTRUCTION TYPE CODE:

I000  
 TOTAL  
 QUANTITY

CODE NO	ITEM	UNIT	QUANTITY
66700110	PERMANENT SURVEY MARKERS TO BE ADJUSTED	EACH	5.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0
67100100	MOBILIZATION	L SUM	1.0
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.0
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8,131.0
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	26,288.0
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	780.0
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	208.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,275.0
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	827.0
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26,288.0
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	780.0
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	208.0
88600100	DETECTOR LOOP, TYPE I	FOOT	1,056.0
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	6,285.0
X4066775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	3,325.0
X7015005	CHANGEABLE MESSAGE SIGNS	CALDA	28.0
Z0004800	BITUMINOUS MIXTURE FOR PATCHING	TON	134.0
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	5.0
*SPECIALTY ITEMS			

Rev.