

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A		X071-2A		X080-2A	Y007	
				RURAL	URBAN	RURAL	URBAN	RURAL	RURAL	URBAN
40600990	TEMPORARY RAMP	SQ YD	1,251	928	323					
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	1,064	532	532					
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	212	106	106					
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	509	314	195					
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	29,753	20,645	9,108					
44000100	PAVEMENT REMOVAL	SQ YD	1,133	945	188					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,916	1,052	864					
44000400	GUTTER REMOVAL	FOOT	1,860	200	1,660					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	664	151	513					
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	3,793	2,333	1,460					
44002500	GUTTER OUTLET REMOVAL	EACH	3		3					
44002805	ISLAND REMOVAL	SQ FT	217	217						
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	1,618		1,618					
44004000	PAVED DITCH REMOVAL	FOOT	365		365					
44004510	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SQ YD	1,748	1,443	305					
48101500	AGGREGATE SHOULDERS, TYPE B 6'	SQ YD	3,371	2,931	440					
48101600	AGGREGATE SHOULDERS, TYPE B 8'	SQ YD	157		157					
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8'	SQ YD	15,010	11,604	3,406					
48300100	PORTLAND CEMENT CONCRETE SHOULDER, 6'	SQ YD	173		173					
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1					1		
50102400	CONCRETE REMOVAL	CU YD	135.9			77.0	58.9			
50104650	SLOPE WALL REMOVAL	SQ YD	1,502			642	860			
50105200	REMOVE EXISTING CULVERTS	EACH	25	19	6					
50200100	STRUCTURE EXCAVATION	CU YD	747			366	310	71		
50300100	FLOOR DRAINS	EACH	24			12	12			
50300225	CONCRETE STRUCTURES	CU YD	394.8			236.3	121.1	37.4		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,249.8			676.2	573.6			
50300260	BRIDGE DECK GROOVING	SQ YD	4,105			2,213	1,892			
50300300	PROTECTIVE COAT	SQ YD	4,620			2,491	2,129			
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	40			20	20			
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	10			10				
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (2" DEPTH)	SQ FT	3,101					3,101		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			.48	.52			
50500505	STUD SHEAR CONNECTORS	EACH	4,260			2,460	1,800			
50800105	REINFORCEMENT BARS	POUND	10,796	66	130	7,160	3,440			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	375,576			205,600	165,430	4,546		
50900205	STEEL RAILING, TYPE SI	FOOT	222					222		
51201400	FURNISHING STEEL PILES HP 10x42	FOOT	448			448				
51201500	FURNISHING STEEL PILES HP 10x57	FOOT	294				294			
51201600	FURNISHING STEEL PILES HP 12x53	FOOT	680					680		

NOTE:
RURAL STA. 942+50.00 TO STA. 1016+00.00
URBAN STA. 1016+00.00 TO STA. 46+80.05
*DENOTES SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
DATE 8/02		SUMMARY OF QUANTITIES SHEET 2 OF 6
DRAWN BY ASB		DRAWN BY ASB
CHECKED BY SJK		CHECKED BY SJK