

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A		X071-2A		X080-2A	Y007	
				RURAL	URBAN	RURAL	URBAN	RURAL	RURAL	URBAN
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	17	12	5					
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	17	12	5					
67100100	MOBILIZATION	L SUM	1	.7	.3					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	.7	.3					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	.7	.3					
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1						
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	78	55	23					
70104490	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 1	EACH	1	.7	.3					
70104495	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 2	EACH	1	.7	.3					
70104500	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 3	EACH	1	.7	.3					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7,287	5,329	1,958					
70300210	TEMPORARY PAVEMENT MARKING, LETTERS & SYMBOLS	SQ FT	1,222	826.8	395.2					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	48,311	35,555	12,756					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4,631	3,185	1,446					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,270	1,270						
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	182	30	152					
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2,746	1,458	1,288					
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS & SYMBOLS	SQ FT	37	37						
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	53,671	40,412	13,259					
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	1,020	1,020						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	24,424	17,723	6,701					
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	1,231	633	598					
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	1,181	633	548					
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,222	826.8	395.2					
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	48,311	35,555	12,756					
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	4,631	3,185	1,446					
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	1,270	1,270						
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	182	30	152					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	952	655	297					
* 78200405	GUARDRAIL MARKERS	EACH	21	16	5					
* 78200500	BARRIER WALL MARKERS	EACH	10	5	5					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	5	3					
78300500	PAINT PAVEMENT MARKING REMOVAL	SQ FT	7,288	5,836	1,452					
Z0002600	BAR SPLICERS	EACH	2,903			1,643	1,260			
* Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1						
* Z0007602	BUILDING REMOVAL NO. 2	L SUM	1	1						
* Z0008236	DRILLED SHAFT IN SOIL 36"	FOOT	169			119	50			
* Z0008330	DRILLED SHAFT IN ROCK 30"	FOOT	128			81	47			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	.7	.3					
Z0023500	FILLING EXISTING CULVERTS	CU YD	6.1	6.1						
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	20	17	3					
Z0028700	GRANULAR SUBGRADE REPLACEMENT	CU YD	1,387	1,387						
Δ Z0030040	IMPACT ATTENUATORS, TEMPORARY (FULLY-REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	4	3	1					
Δ Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY-REDIRECTIVE), TEST LEVEL 2	EACH	4	3	1					

Δ SFTY 3-N

NOTE:
RURAL STA. 942+50.00 TO STA. 1016+00.00
URBAN STA. 1016+00.00 TO STA. 46+80.05
* DENOTES SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SUMMARY OF QUANTITIES
SHEET 5 OF 6

DRAWN BY ASB
CHECKED BY SJK

DATE 8/02