

steffenmk
2/8/2005
c:\projects\94888d\05703pa.dgn

SUMMARY OF QUANTITIES

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
821	(142)TS-3	JEFFERSON	9	3
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT NO.	

CONTRACT NO. 94888

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		Y031-1F 50% STATE 50% CITY	Y030-1E 100% CITY
* 42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	943	943	
* 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	40	40	
* 44004700	SIDEWALK REMOVAL (SPECIAL)	SQ FT	1223	1223	
* 60604500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (ABUTTING EXISTING PAVEMENT)	FOOT	40	40	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	8	8	
* 72000200	SIGN PANEL - TYPE 2	SQ FT	20	20	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	515	515	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	28	28	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	117	117	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	409	409	
80500205	SERVICE INSTALLATION, TYPE B (MODIFIED)	EACH	1	1	
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	105	54	51
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	68	38	30
81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	395	198	197
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	32		32
81400100	HANDHOLE	EACH	7	3	4
81400300	DOUBLE HANDHOLE	EACH	1	1	
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	173	92	81
81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	143		143
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	3		3
83028300	LIGHT POLE, STEEL, 30 FT. M.H., 8 FT. MAST ARM	EACH	1	1	
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	3	3	
84200700	LIGHTING FOUNDATION REMOVAL	EACH	3	3	
86300300	CONTROLLER CABINET TYPE III	EACH	1	1	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		Y031-1F 50% STATE 50% CITY	Y030-1E 100% CITY
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1343	1343	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	484	484	
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	31	31	
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1	1	
87702860	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 26 FT.	EACH	1	1	
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	1	1	
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5	3.5	
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10	10	
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	35	35	
88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	9	9	
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8	8	
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2	2	
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	7	7	
X8810495	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	4	4	

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY