

SUMMARY OF QUANTITIES

FBI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9376	00-00017-00-RP	ST. CLAIR	33	3
SUMMARY OF QUANTITIES				

CONTRACT NO. 97242

SUMMARY OF QUANTITIES			
J000-2A			
CODE NO	ITEM	UNIT	QTY
20200100	EARTH EXCAVATION	CU YD	3,777
20800150	TRENCH BACKFILL	CU YD	737
21400100	GRADING AND SHAPING DITCHES	FOOT	25
25000100	SEEDING, CLASS 1	ACRE	0.6
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	47
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	47
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	47
25100115	MULCH, METHOD 2	ACRE	0.6
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	75
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	0.6
28000400	PERIMETER EROSION BARRIER	FOOT	3,000
28000500	INLET AND PIPE PROTECTION	EACH	55
28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD	8
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	8
30200650	PROCESSING MODIFIED SOILS 12"	SQ YD	10,031
31001500	LIME	TON	194
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	2,150
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SQ YD	15
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	136
42000200	PORTLAND CEMENT CONCRETE PAVEMENT 7"	SQ YD	8,667
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	138
42301100	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, SPECIAL (4 INCH)	SQ YD	135
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	8,796
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	155
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	470
44000600	SIDEWALK REMOVAL	SQ FT	1,918
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	5
50105220	PIPE CULVERT REMOVAL	FOOT	113
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTION 18"	EACH	2
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	892
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	237
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	282
55034300	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19	FOOT	1,118
55034400	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 34, RISE 22	FOOT	276
56107100	REMOVE AND RELOCATE WATERMAIN, 6"	FOOT	150
56107200	REMOVE AND RELOCATE WATERMAIN, 8"	FOOT	115
56107400	REMOVE AND RELOCATE WATERMAIN, 12"	FOOT	80

SUMMARY OF QUANTITIES			
J000-2A			
CODE NO	ITEM	UNIT	QTY
60224039	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1
60224090	MANHOLES, TYPE A, 6'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	11
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	6
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	5
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	12
60242500	INLETS, SPECIAL, NO. 1	EACH	15
60242600	INLETS, SPECIAL, NO. 2	EACH	1
60242700	INLETS, SPECIAL, NO. 3	EACH	2
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3,483
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70104490	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 1	EACH	1
70104495	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 2	EACH	1
70104500	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 3	EACH	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	60
70300200	TEMPORARY PAVEMENT MARKING	FOOT	4815
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	20
72000100	SIGN PANEL-TYPE 1	SQ FT	31
72900100	METAL POST-TYPE A	FOOT	64
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	42
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	6,012
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	769
78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	249
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	40
X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	100
XX002053	LANDSCAPE RESTORATION	L SUM	1
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	95
Z0077700	WOOD FENCE TO BE REMOVED AND REERECTED	FOOT	135
XX006174	PEDESTRIAN BRIDGE REMOVAL	EACH	1