


SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			
CODE NO.	ITEM DESCRIPTION	UNIT	Y031-IF TOTAL QUANTITY
20800150	TRENCH BACKFILL	CU YD	7
25000910	SEEDING, CLASS I (MODIFIED)	ACRE	0.50
25100110	MULCH, METHOD 1	TON	1
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	319
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	247
42001200	PAVEMENT FABRIC	SQ YD	247
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	970
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4"	SQ FT	726
44000100	PAVEMENT REMOVAL	SQ YD	1168
44000300	CURB REMOVAL	FOOT	135
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	658
44000600	SIDEWALK REMOVAL	SQ FT	402
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1
60600605	CONCRETE CURB, TYPE B	FOOT	311
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	471
67100100	MOBILIZATION	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ FT	18
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	250
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	98
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	56
80500105	SERVICE INSTALLATION, TYPE A (MODIFIED)	EACH	1
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	87
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	71
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	5
81018400	CONDUIT PUSHED, 1 1/2" DIA., GALVANIZED STEEL	FOOT	45

SUMMARY OF QUANTITIES			
CODE NO.	ITEM DESCRIPTION	UNIT	Y031-IF TOTAL QUANTITY
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	62
81400400	CONCRETE HANDHOLE	EACH	2
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	163
85700105	FULL-ACTUATED CONTROLLER AND TYPE III CABINET, SPECIAL	EACH	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	187
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	201
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	743
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE NO. 6 3C	FOOT	5
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	2
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	2
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6
87800210	CONCRETE FOUNDATION, TYPE D (SPECIAL)	FOOT	3
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	20
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	4
X0323553	ORNAMENTAL FENCE, WROUGHT IRON	FOOT	774
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4
X8810395	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	2
X8880010	ADA PEDESTRIAN PUSH-BUTTON	EACH	2
XX003182	BOLLARDS COMPLETE (SET OF 3)	EACH	1
XX003360	STORM SEWER PVC (SDR 26), 12"	FOOT	37
XX003592	BOLLARD ASSEMBLY	EACH	1

FINAL SURVEY PLOTTED	BY	DATE
NOTE BOOK TEMPLATE AREAS CHECKED		
NO.		

ORIGINAL SURVEY PLOTTED	BY	DATE
NOTE BOOK TEMPLATE AREAS CHECKED		
NO.		

 Junco Associates, Inc. P.C. CONSULTING ENGINEERS AND LAND SURVEYORS 2102 State Street, P.O. Box 1325 / 100 North Dearborn Street Granite City, Illinois 62040 / Granite City, Illinois 62040 Phone: (618) 937-1400 / (618) 937-5535 / Fax: (618) 937-5541 / (618) 937-9541		SUMMARY OF QUANTITIES GRANITE CITY SENIOR HIGH SCHOOL GRANITE CITY, ILLINOIS SECTION No. 02-00183-00-TL																	
REVISIONS <table border="1"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>BY</th> <th>REMARKS</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>		NO.	DATE	BY	REMARKS													SCALE: N.T.S. DSN. BY: BFK DATE: 11/18/04 DWN. BY: WRC DATE: 11/18/04 CHK'D: BFK DATE: 11/18/04 DWG. NO. JOB NO. 020210 DGN. NAME: SUMQTY OF 16 SHTS	
NO.	DATE	BY	REMARKS																
		SHEET 3																	