



- 1-1/2" PVC FORCE MAIN
- PAINT PAVEMENT MARKING LINE 6"
- STA. 48+54 RT. TO STA. 48+85.09 RT, 526'
- EXCAVATION (SPECIAL)
- STA. 48+67 RT. TO STA. 48+85 RT., 17.7 CU. YD.
- CONCRETE PAVEMENT (ADA PARKING STALLS)
- STA. 48+67 RT. TO STA. 48+88 RT, 64.0 SQ. YD.
- 4" SUB BASE GRANULAR MATERIAL (TYPE B)
- STA. 48+67 RT. TO STA. 48+88 RT., 64.0 SQ. YD.
- PAINT PAVEMENT MARKING LETTERS AND SYMBOLS
- STA. 48+87, 9.2 SQ. FT.
- MATCH EXISTING ELEVATION, BUTT JOINT

TREE REMOVAL SCHEDULE		
STA.	OFFSET	SIZE
48+55LT	47'	10"
48+57LT	50'	7"
50+52LT	25'	15"

- DEBRIS REMOVAL
- PROPOSED AGGREGATE SURFACE COURSE
- HMA SURFACE REMOVAL - BUTT JOINT
- CLASS D PATCHES
- STONE RIPRAP
- GATE REMOVAL
- PROPOSED GATE
- PIPE AND INLET PROTECTION
- PERIMETER EROSION BARRIER

FILE NAME =	USER NAME = #USER#	DESIGNED - R.H.D.	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>ARGYLE LAKE STATE PARK MAIN ROAD</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL#		DRAWN - J.T.T.	REVISED -			ARGYLE LAKE STATE PARK	MCDONOUGH	162	26	
		CHECKED - T.T.P.	REVISED -			CONTRACT NO. 46158				
		DATE - 12/09/10	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
						SCALE: 1" = 20'	SHEET NO. 26 OF 162 SHEETS	STA. 47+50 TO STA. 51+75		