



GUARD POSTS		
STA.	OFFSET	EACH
504+43	25.99	1
504+51	31.71	1
504+57	37.45	1
504+64	43.19	1
504+71	49.37	1
504+77	56.22	1
504+83	62.84	1
504+95	56.26	1
505+23	44.47	1
505+25	35.69	1
505+27	26.92	1
505+29	18.15	1
505+31	9.38	1
505+33	0.61	1

☒ SCARIFY EXISTING SURFACE

/// STEEL PLATE BEAM GUARDRAIL REMOVAL

● PROPOSED GUARDPOST

MATCHLINE 500+75
PC Sta. 500+81.01

EXIST. CURVE C123
PI STA. = 501+46.92
Δ = 47° 26' 20" (LT)
D = 38° 11' 50"
R = 150.00'
T = 65.91'
L = 124.19'
E = 13.84'
P.C. STA. = 500+81.01
P.T. STA. = 502+05.20

SCARIFY EXISTING SURFACE
STA. 500+75 TO STA. 505+25, 965.1 SQ. YD.

PI Sta. 502+05.20

POT Sta. 502+64.59

POT Sta. 503+52.85

CONTROL POINT #101
STA. 504+56.10, 4.12' RT.
N 1380653.31
E 2123830.87
ELEV. = 686.85

GUARDRAIL REMOVAL
STA. 505+22 LT. TO STA. 505+35 LT., 48'

POT Sta. 505+44.29

WOOD GUARDRAIL REMOVAL
STA. 504+46 RT. TO STA. 504+96 RT., 63'

FILE NAME =	USER NAME = #USER#	DESIGNED - R.H.D.	REVISED -
#FILEL#		DRAWN - J.T.T.	REVISED -
	PLOT SCALE = #SCALE#	CHECKED - T.T.P.	REVISED -
	PLOT DATE = #DATE#	DATE - 12/09/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ARGYLE LAKE STATE PARK
SIDE ROAD**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	ARGYLE LAKE STATE PARK	MCDONOUGH	162	84
CONTRACT NO. 46158				
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCALE: 1" = 20' SHEET NO. 84 OF 162 SHEETS STA. 500+75 TO STA. 505+44.29