

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				0001	0040	0010	0008	0021
40600300	AGGREGATE (PRIME COAT)	TON	3	3				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	145	145				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2,100	2,100				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	171	171				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,868	1,868				
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	620	620				
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	84,581	84,581				
42001300	PROTECTIVE COAT	SQ YD	128,936	128,936				
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	2,237	2,237				
44000100	PAVEMENT REMOVAL	SQ YD	67,105	67,105				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,261	1,261				
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	1,126	1,126				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	4,780	4,780				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,384	1,384				
44004000	PAVED DITCH REMOVAL	FOOT	32	32				
44004250	PAVED SHOULDER REMOVAL	SQ YD	23,910	23,910				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	7,783	7,783				
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	42	42				
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	7,430	7,430				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	95	95				
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	16,627	16,627				
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	28,400	28,400				
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1		
50200100	STRUCTURE EXCAVATION	CU YD	11,829		11,600	146		83
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	5,207	2,014	2,440	38	65	650
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	2,318		2,000	24	294	
50300225	CONCRETE STRUCTURES	CU YD	6,634.2		5,873.5	247.5	377.2	136
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,345.1			667.6	677.5	
50300260	BRIDGE DECK GROOVING	SQ YD	2,782			1,302	1,480	
50300280	CONCRETE ENCASEMENT	CU YD	7.6			7.6		
50300300	PROTECTIVE COAT	SQ YD	3,159			1,409	1,750	
50400735	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"	FOOT	1,501			1,501		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1				1	
50500505	STUD SHEAR CONNECTORS	EACH	2,046				2,046	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,097,007	2,250	658,020	188,580	238,460	4,297

* DENOTES SPECIALTY ITEM

FILE NAME = D:\60F12-SHT-S0082.dgn

USER NAME = TKluegel
 PLOT SCALE = 1:50
 PLOT DATE = 2/4/2011

DESIGNED - MJT
 DRAWN - MJT
 CHECKED - DLT
 DATE - 2/4/11

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 2 OF 11 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99-2HB-2B-1	WILL	756	6
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60F12	

Rev. 4-14-11

Rev.