



CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				0001	0040	0010	0008	0021
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	6	6				
* X0324234	2070 LITE CONTROLLER	EACH	8					8
* X0324236	BUCK-BOOST TRANSFORMER, 1.5KVA, 240V PRIMARY, 24V SECONDARY	EACH	13					13
* X0324237	CLOSED CIRCUIT TELEVISION DOME CAMERA HIGH MAST TOWER INSTALLATION	EACH	2					2
* X0324245	CONCRETE FOUNDATION, SURVEILLANCE CABINET, MODEL 334	EACH	5					5
* X0324248	DETECTOR RACK	EACH	5					5
* X0324263	REMOVAL OF EXISTING HIGH MAST LIGHT TOWER, SALVAGE	EACH	12					12
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	4,555	4,555				
* X0029654	HIGH TENSION CABLE MEDIAN BARRIER TERMINALS	EACH	2	2				
* X0325040	FIBER OPTIC INNERDUCT 1 1/4" DIA.	FOOT	25,235					25,235
* X0029652	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	11,065	11,065				
X0326020	UTILITY PROTECTION PAD	SQ YD	911	911				
* X0029653	HIGH TENSION CABLE MEDIAN BARRIER DEMONSTRATION	EACH	1	1				
* X0326266	ETHERNET SWITCH	EACH	8					8
* X0326323	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR, STAINLESS STEEL HOUSING	EACH	8					8
* X0326465	MODIFICATION OF EXISTING VIDEO DISTRIBUTION SYSTEM	L SUM	1					1
* X0326492	REMOVAL OF EXISTING SIGN LIGHTING UNIT AND SALVAGE	EACH	2	2				
X2020502	BRACED EXCAVATION	CU YD	347			224	123	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	294			294		
* X2502024	SEEDING, CLASS 4B (MODIFIED)	ACRE	2.6					2.6
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	4	4				
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	22,820	22,820				
* X5011100	FOUNDATION REMOVAL	EACH	12					12
X5210110	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 200K	EACH	14				14	
X5210335	HIGH LOAD MULTI-ROTATIONAL BEARINGS, FIXED - 450K	EACH	7				7	
X6020294	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1				
X6060200	CONCRETE MEDIAN, TYPE SB-6.24 (MODIFIED)	SQ FT	5,991	5,991				
X6061310	CONCRETE MEDIAN SURFACE, 4 INCH (SPECIAL)	SQ FT	13,109	13,109				
X6640200	TEMPORARY CHAIN LINK FENCE	FOOT	1,925	1,925				
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	18	18				
X6700600	ENGINEER'S FIELD LABORATORY (SPECIAL)	CAL MO	18	18				
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	809	809				
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	138,743	138,743				
X7030035	WET REFLECTIVE TEMPORARY TAPE TYPE III, 5 INCH	FOOT	10,208	10,208				
X7030045	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	4,678	4,678				
X7030050	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	1,582	1,582				

* DENOTES SPECIALTY ITEM

Rev. 4-14-11

Rev.

FILE NAME = D:\60F12-SHT-S0009.dgn	USER NAME = TKLuegel	DESIGNED - MJT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE. 55	SECTION 99-2HB-2B-1	COUNTY WILL	TOTAL SHEETS 756	SHEET NO. 13
PLOT SCALE = 1/80	CHECKED - DLT	REVISED -	REVISED -		SCALE: NONE	SHEET NO. 9 OF 11 SHEETS	STA. TO STA.	CONTRACT NO. 60F12				
PLOT DATE = 2/4/2011	DATE - 2/4/11	REVISED -	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT							