

EARTHWORK SCHEDULE ARSENAL ROAD - TEMPORARY PAVEMENT

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL / UNSUITABLE EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	POROUS GRANULAR EMBANKMENT, SUBGRADE	ROCK EXCAVATION
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
913+00.00	914+00.00	8	0	7	6	1	0	0
914+00.00	915+00.00	17	0	14	8	6	0	0
915+00.00	916+00.00	21	0	18	2	16	0	0
916+00.00	917+00.00	23	0	20	2	18	0	0
917+00.00	918+00.00	23	0	20	2	18	0	0
918+00.00	919+00.00	23	0	20	0	20	0	0
919+00.00	920+00.00	23	0	20	0	20	0	0
920+00.00	921+00.00	25	0	21	0	21	0	0
921+00.00	922+00.00	26	0	22	0	22	0	0
922+00.00	923+00.00	26	0	22	0	22	0	0
923+00.00	924+00.00	26	0	22	0	22	0	0
924+00.00	925+00.00	26	0	22	0	22	0	0
925+00.00	926+00.00	26	0	22	0	22	0	0
926+00.00	927+00.00	28	0	24	0	24	0	0
927+00.00	928+00.00	30	0	26	0	26	0	0
928+00.00	929+00.00	28	0	24	0	24	0	0
929+00.00	930+00.00	26	0	22	0	22	0	0
930+00.00	931+00.00	28	0	24	0	24	0	0
931+00.00	932+00.00	32	0	27	0	27	0	0
932+00.00	933+00.00	32	0	27	0	27	0	0
933+00.00	934+00.00	28	0	24	0	24	0	0
934+00.00	935+00.00	26	0	22	0	22	0	0
935+00.00	936+00.00	25	0	21	0	21	0	0
936+00.00	937+00.00	23	0	20	0	20	0	0
937+00.00	938+00.00	23	0	20	2	18	0	0
938+00.00	939+00.00	21	0	18	6	12	0	0
939+00.00	940+00.00	21	0	18	6	12	0	0
940+00.00	941+00.00	23	0	20	2	18	0	0
941+00.00	942+00.00	25	0	21	0	21	0	0
942+00.00	943+00.00	23	0	20	2	18	0	0
943+00.00	944+00.00	21	0	18	2	16	0	0
944+00.00	945+00.00	25	0	21	2	19	0	0
945+00.00	946+00.00	28	0	24	2	22	0	0
946+00.00	947+00.00	30	0	26	0	26	0	0
947+00.00	948+00.00	28	0	24	0	24	0	0
948+00.00	949+00.00	26	0	22	0	22	0	0
949+00.00	950+00.00	13	0	11	0	11	0	0
SUB TOTAL		906	0	774	44	730	0	0

\* ASSUME 15% FOR SHRINKAGE

FILE NAME = D160F12-SHT-SCHEDULE01.dgn	USER NAME = TKLuegel	DESIGNED - TRK	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.I. RTE. 55	SECTION 99-2HB-2B-1	COUNTY WILL	TOTAL SHEETS 756	SHEET NO. 26
PLOT SCALE = 1:50	CHECKED - DLT	REVISED -	SCALE: NONE					SHEET NO. 1 OF 8 SHEETS	STA.	TO STA.	CONTRACT NO. 60F12	
PLOT DATE = 2/3/2011	DATE - 2/4/11	REVISED -				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT						