

SUMMARY OF QUANTITIES

					ROADWAY 80% FED 20% STATE	BOX CULVERT 80% FED. 20% STATE	ROADWAY LIGHTING 80% FED. 20% STATE	WATER MAIN 100% VILLAGE OF MELROSE PARK	WATER MAIN 90% STATE 10% VILLAGE OF MELROSE PARK	SANITARY 75% STATE 25% VILLAGE OF MELROSE PARK
			URBAN TOTAL QUANTITY							
CODE NO.	PAY ITEM DESCRIPTION	UNIT			0004	0011	0021	0043	0043	0043
Z0067700	STEEL CASING 20"	FOOT	150						50	100
Z0067900	STEEL CASINGS 24"	FOOT	80							
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	2,719			2,719				
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1			1				
Z0076600	TRAINEES	HOOR								
* A2005014	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	3		3					
* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	3		3					
* C2C05724	SHRUB, RHUS AROMATICA (FRAGRANT SUMAC), 2' WIDTH, CONTAINER	EACH	20		20					
X0322080	BUS SHELTER REMOVE AND RELOCATE	EACH	1		1					
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	897			897				
* X0324456	DRILLING AND SETTING SOLDIER PILES (IN ROCK)	CU FT	2,439			2,439				
X0326299	TEMPORARY SIGN PANEL ASSEMBLY	SQ FT	7		7					
X0326712	ABANDON AND FILL EXISTING SANITARY SEWER	EACH	1							1
X5610651	ABANDON EXISTING WATER MAIN, FILL WITH CLSM	FOOT	264					245	19	
X5610004	DUCTILE IRON WATER MAIN FITTINGS	POUND	4,465					2,355	2,110	
X0350810	BOLLARD REMOVAL	EACH	6		6					
X0487700	SANITARY SEWER REMOVAL 10"	FOOT	103							103
* X0502600	TEMPORARY LIGHTING	L SUM	1				1			
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	45		15				30	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	6		6					
X4023000	TEMPORARY ACCESS (ROAD)	EACH	1		1					
X5610708	WATER MAIN REMOVAL, 8"	FOOT	128						128	
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	4		4					
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	10,573		10,573					
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	54		54					
* X0440110	RELOCATE EXISTING LIGHTING UNIT, SPECIAL	EACH	10				10			
X0326712	ABANDON AND FILL EXISTING SANITARY SEWER	EACH	16							16
X0327221	DUCTILE IRON WATER MAIN, 12" IN STEEL CASING	FOOT	130					80	50	
XX003032	GATE VALVES 12"	EACH	1						1	
* K1001908	IRRIGATION SYSTEM SPECIAL	L SUM	1		1					
X0327222	SANITARY MANHOLES, TYPE A, 4'-DIAMETER	EACH	2							2
X6026055	SANITARY MANHOLE, SPECIAL	EACH	2							2
X0327223	SANITARY SEWER, 8" CONCRETE ENCASEMENT	FOOT	66							66
X0327224	SANITARY SEWER, 10" CONCRETE ENCASEMENT	FOOT	66							66
X0327225	SANITARY SEWER, 8" IN STEEL CASING	FOOT	52							52
X0327226	SANITARY SEWER, 10" IN STEEL CASING	FOOT	52							52
X0327227	GATE VALVE, 8" WITH VALVE BOX	EACH	2					1	1	
X0327228	VALVE VAULTS, TYPE A, TYPE 1 FRAME, CLOSED LID, SPECIAL	EACH	3					2	1	
X0327229	SLIDE GATE	EACH	1							1

* SPECIALTY ITEM



USER NAME = #USER#
PLOT SCALE = #SCALE#
PLOT DATE = 1/27/2011

DESIGNED - KAC
DRAWN - TMF
CHECKED - KAC
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
LAKE STREET OVER POISON CREEK

SCALE: N.T.S. SHEET NO. 5 OF 5 SHEETS

SECTION
3264-T
COUNT
COOK
CONTRACT
ILLINOIS FED. AID PROJECT

Rev
TOTAL SHEETS
110
NO. 60441