

# SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY	BOX CULVERT	ROADWAY	WATER MAIN	WATER MAIN	SANITARY
				80% FED 20% STATE	80% FED 20% STATE	LIGHTING 80% FED 20% STATE	100% VILLAGE OF MELROSE PARK	90% STATE 10% VILLAGE OF MELROSE PARK	75% STATE 25% VILLAGE OF MELROSE PARK
				0004	0011	0021	0043	0043	0043
60500050	REMOVING CATCH BASINS	EACH	13	13					
60600605	CONCRETE CURB, TYPE B	FOOT	45	45					
60602800	CONCRETE GUTTER, TYPE B	FOOT	45	45					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	180	180					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,986	1,986					
<del>60601008</del>	<del>FLAP GATE 8"</del>	<del>EACH</del>	<del>1</del>						<del>1</del>
<del>60601010</del>	<del>FLAP GATE 10"</del>	<del>EACH</del>	<del>1</del>						<del>1</del>
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	100.0	100.0					
63200310	GUARDRAIL REMOVAL	FOOT	101	101					
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2					
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	133	133					
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	5	5					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBLIZATION	L SUM	1	1					
<del>70100460</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701000</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	60					
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,633	3,633					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,175	1,175					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	325	325					
70500100	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	50	50					
70500615	TEMPORARY TRAFFIC BARRIER TERMNAL, TYPE 1	EACH	1	1					
* 78008200	POLYUREA PAVEMENT MARKING TYPE I- LETTERS AND SYMBOLS	SQ FT	354	354					
* 78008210	POLYUREA PAVEMENT MARKING TYPE I- LINE 4"	FOOT	3,183	3,183					
* 78008230	POLYUREA PAVEMENT MARKING TYPE I- LINE 6"	FOOT	454	454					
* 78008250	POLYUREA PAVEMENT MARKING TYPE I- LINE 12"	FOOT	107	107					
* 78008270	POLYUREA PAVEMENT MARKING TYPE I- LINE 24"	FOOT	74	74					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	145	145					
<del>78100200</del>	<del>TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER</del>	<del>EACH</del>	<del>53</del>	<del>53</del>					
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4					
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	376	376					

\* SPECIALTY ITEM

\* SPECIALTY ITEM

FILE NAME = G:\ENR\08-6790-17 Lake St. Triple Box Culvert\0806\01\Sht\018044-INT-500.dgn



USER NAME = #USER*	DESIGNED - KAC	REVISED -
PLOT SCALE = #SCALE*	DRAWN - TMF	REVISED -
PLOT DATE = 1/27/2011	CHECKED - KAC	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
LAKE STREET OVER ADDISON CREEK**

SCALE: N.T.S.      SHEET NO. 3 OF 5 SHEETS

F.A.U. RTE.	SECTION	COUNT
3537	3264-T	200
		CONT
ILLINOIS FED. AID PROJEC		

TOTAL SHEET NO.	SHEET NO.
110	6
NO. 60H44	