

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY	BOX CULVERT	ROADWAY	WATER MAIN	WATER MAIN	SANITARY
				80% FED 20% STATE	80% FED. 20% STATE	LIGHTING 80% FED. 20% STATE	100% VILLAGE OF MELROSE PARK	90% STATE 10% VILLAGE OF MELROSE PARK	75% STATE 25% VILLAGE OF MELROSE PARK
				CONSTRUCTION TYPE CODE					
				0004	0011	0021	0043	0043	0043
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3,181	3,181					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	180	180					
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	442	275		167			
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	11.5	11.5					
* 81100800	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL	FOOT	110			110			
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	86	86					
* 81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"X12"X6"	EACH	2			2			
* 81018700	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	78	78					
* 81400100	HANDHOLE	EACH	2	2					
* 81300245	ELECTRIC CABLE IN TRENCH, SIGNAL, NO. 14 5C	FOOT	728	728					
* 81400200	HEAVY-DUTY HANDHOLE	EACH	1	1					
* 81300255	ELECTRIC CABLE IN TRENCH, SIGNAL, NO. 14 7C	FOOT	441	441					
* 81603050	UNIT DUCT, 600V, 3-1C NO. 6, 1/2" DIA. POLYETHYLENE	FOOT	1,092			1,092			
* 81800330	AERIAL CABLE, 3-1C NO. 6 WITH MESSENGER WIRE	FOOT	320			320			
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,358	306		1,032			
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	90			90			
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	10			10			
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	10			10			
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1					
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAR	FOOT	703	703					
* 87900200	DRILL EXISTING HANDHOLE	EACH	3	3					
* 88600100	DETECTOR LOOP, TYPE I	FOOT	80	80					
* 88600700	PERFORMED DETECTOR LOOP	FOOT	164	164					
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	427	427					
89502380	REMOVE EXISTING HANDHOLE	EACH	3	3					
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	8,220	8,220					
* Z0007118	UNTREATED TIMBER LAGGING	SQ FT	1,162		1,162				
* Z0007510	ENGINEERED BARRIER	SQ YD	889	889					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Z0016702	DETOUR SIGNING	L SUM	1	1					
* Z0028404	FURNISHING SOLDIER PILES (W SECTION)	FOOT	953		953				
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3	3					
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4					
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	286	286					
* Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6			6			
* Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1	1					
Z0033066	PERFORMED DETECTOR LOOP	FOOT	198	198					
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	250	250					
Z0044800	PRESSURE CONNECTION 8"X8"	EACH	2			1	1		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	150		150				
Z0057000	SANITARY SEWER 10"	FOOT	24						24
Z0062456	TEMPORARY PAVEMENT	SQ YD	123	123					

* SPECIALTY ITEM

FILE NAME = G:\END\06-6799-17 Lake St. Triple Box Culvert\CAD\Civil\Sheet\06044-shr-500.dgn



USER NAME = #USER*	DESIGNED - KAC	REVISED -
PLOT SCALE = #SCALE*	DRAWN - TMF	REVISED -
PLOT DATE = 1/27/2011	CHECKED - KAC	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
LAKE STREET OVER ADDISON CREEK**

SCALE: N.T.S. SHEET NO. 4 OF 5 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	3264-T	COOK	10	7
CONTRACT NO. 60H44			Rev.	

ILLINOIS FED. AID PROJECT