

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY	BOX CULVERT	ROADWAY	WATER MAIN	WATER MAIN	SANITARY
				80% FED 20% STATE	80% FED. 20% STATE	LIGHTING 80% FED. 20% STATE	100% VILLAGE OF MELROSE PARK	90% STATE 10% VILLAGE OF MELROSE PARK	75% STATE 25% VILLAGE OF MELROSE PARK
				0004	0011	0021	0043	0043	0043
Z0067700	STEEL CASING 20"	FOOT	150					50	100
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	2,719		2,719				
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1		1				
Z0076600	FRAMES	HOURL							
* A2005014	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	3	3					
* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	3	3					
* C2C05724	SHRUB, RHUS AROMATICA (FRAGRANT SUMAC), 2' WIDTH, CONTAINER	EACH	20	20					
X0322080	BUS SHELTER REMOVE AND RELOCATE	EACH	1	1					
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	897		897				
* X0324456	DRILLING AND SETTING SOLDIER PILES (IN ROCK)	CU FT	2,439		2,439				
X0326299	TEMPORARY SIGN PANEL ASSEMBLY	SQ FT	7	7					
X0326712	ABANDON AND FILL EXISTING SANITARY SEWER	EACH	1						1
X5610651	ABANDON EXISTING WATER MAIN, FLL WITH CLSM	FOOT	19					19	
X5610004	DUCTILE IRON WATER MAIN FITTINGS	POUND	3,080				955	2,125	
X0350810	BOLLARD REMOVAL	EACH	6	6					
X0487700	SANITARY SEWER REMOVAL 10"	FOOT	103						103
* X0502600	TEMPORARY LIGHTING	L SUM	1			1			
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	45	15				30	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	6	6					
X4023000	TEMPORARY ACCESS (ROAD)	EACH	1	1					
X5610708	WATER MAIN REMOVAL, 8"	FOOT	128					128	
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	4	4					
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	10,573	10,573					
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	54	54					
* X0440110	RELOCATE EXISTING LIGHTING UNIT, SPECIAL	EACH	10			10			
X0326712	ABANDON AND FILL EXISTING SANITARY SEWER	EACH	10						10
X0327221	DUCTILE IRON WATER MAIN, 12" IN STEEL CASING	FOOT	50					50	
XX003032	GATE VALVES, 12"	EACH	1					1	
* K1001900	IRRIGATION SYSTEM SPECIAL	L SUM	1	1					
X0327222	SANITARY MANHOLES, TYPE A, 4'-DIAMETER	EACH	2						2
X0026055	SANITARY MANHOLE, SPECIAL	EACH	2						2
X0327223	SANITARY SEWER, 8" CONCRETE ENCASEMENT	FOOT	66						66
X0327224	SANITARY SEWER, 10" CONCRETE ENCASEMENT	FOOT	66						66
X0327225	SANITARY SEWER, 8" IN STEEL CASING	FOOT	52						52
X0327226	SANITARY SEWER, 10" IN STEEL CASING	FOOT	52						52
X0327227	GATE VALVE, 8" WITH VALVE BOX	EACH	1				1		
X0327228	VALVE VAULTS, TYPE A, TYPE 1 FRAME, CLOSED LID, SPECIAL	EACH	3				1	2	
X0327229	SLIDE GATE	EACH	1						1

* SPECIALTY ITEM

FILE NAME = G:\ENR\06-6790-17 Lake St. Trf., Box Culvert\CAD\Civil\Sheet\060444-Int-500.dgn



USER NAME = #USER#	DESIGNED - KAC	REVISED -
PLOT SCALE = #SCALE#	DRAWN - TMF	REVISED -
PLOT DATE = 1/27/2011	CHECKED - KAC	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES LAKE STREET OVER MADISON CREEK	
SCALE: N.T.S.	SHEET NO. 5 OF 5 SHEETS

SECTION 3264-T	COUNT COOK	TOTAL SHEETS 110	SHEET NO. 8
CONTRACT NO. 60444		ILLINOIS FED. AID PROJECT	

Rev.