

60100060 CONCRETE HEADWALL FOR PIPE DRAINS				
EACH	LOCATION			REMARKS
1	LT. STA. & OFFSET	436+62.90	35.0	TRANSVERSE UNDERDRAINS
1	RT. STA. & OFFSET	436+63.10	35.6	
1	LT. STA. & OFFSET	439+04.70	32.8	
1	LT. STA. & OFFSET	443+00.00	32.9	
1	LT. STA. & OFFSET	444+80.00	34.9	
5	TOTAL			

63200310 GUARDRAIL REMOVAL				
FOOT	LOCATION			REMARKS
126	LT. STA.	439+79.80	TO	441+08.50
126	RT. STA.	439+86.60	TO	441+09.70
126	LT. STA.	441+85.20	TO	443+12.50
63	RT. STA.	441+83.90	TO	442+46.70
441	TOTAL			

60107600 PIPE UNDERDRAINS 4"				
FOOT	LOCATION			REMARKS
64	436+63.10			TRANSVERSE UNDERDRAINS
44	439+04.72			
44	443+00.00			
46	444+80.00			
33	447+80.00			
297	444+80.00	TO	447+80.00	LONGITUDINAL UNDERDRAIN
528	TOTAL			

63500105 DELINEATORS				
EACH	LOCATION			REMARKS
2	431+50.00			
2	434+50.00			
2	436+50.00			
2	438+50.00			PC (448+55.37)
2	439+75.00			
2	441+00.00			
2	442+25.00			
2	443+50.00			
2	444+75.00			
2	446+00.00			
2	447+25.00			
2	448+50.00			PT (448+44.54)
2	450+50.00			
2	452+50.00			
1	435+75.00	RT. STA.		GUARDRAIL TERMINAL
1	435+75.00	LT. STA.		GUARDRAIL TERMINAL
1	443+65.70	RT. STA.		GUARDRAIL TERMINAL
1	444+64.70	LT. STA.		GUARDRAIL TERMINAL
1	434+32.00	LT. STA.		CULVERT
1	435+33.00	LT. STA.		CULVERT
1	443+46.00	RT. STA.		CULVERT
1	444+16.00	RT. STA.		CULVERT
1	436+62.90	LT. STA.		HEADWALL
1	436+63.10	RT. STA.		HEADWALL
1	439+04.70	LT. STA.		HEADWALL
1	443+00.00	LT. STA.		HEADWALL
1	444+80.00	LT. STA.		HEADWALL
41	TOTAL			

60600095 CLASS SI CONCRETE (OUTLET)				
LOCATION		FOOT	CU YD	COMMENT
445+43.98	19' LT	VAR	1.90	A-A TO E-E
		18	1.22	E-E TO F-F
449+53.82	19' LT	VAR	0.22	C-C to B'-B'
		4	0.30	B'-B' to End
TOTAL =			3.7	

61133100 FIELD TILE JUNCTION VAULTS, 2' DIA.				
EACH	LOCATION			REMARKS
2	430+41.60	TO	450+50.20	FIELD TILE REPAIR AS DIRECTED BY R.E.
2	TOTAL			

63000001 STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS				
FOOT	LOCATION			REMARKS
400.0	LT. STA.	436+25.70	TO	440+27.80
187.5	LT. STA.	442+32.10	TO	444+22.00
412.5	RT. STA.	436+20.10	TO	440+30.30
87.5	RT. STA.	442+29.90	TO	443+16.30
1,087.5	TOTAL			

64200105 SHOULDER RUMBLE STRIP				
FOOT	LOCATION			REMARKS
344	LT. STA.	431+41.60	TO	434+85.04
521	LT. STA.	435+35.10	TO	440+55.54
928	RT. STA.	431+29.02	TO	440+56.80
584	LT. STA.	442+04.35	TO	447+88.05
232	LT. STA.	448+18.85	TO	450+50.00
176	RT. STA.	442+03.29	TO	443+78.58
644	RT. STA.	444+06.10	TO	450+50.00
3,429	TOTAL			

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6				
EACH	LOCATION			REMARKS
1	LT. STA.	440+27.80	TO	440+71.50
1	RT. STA.	440+30.30	TO	440+73.00
1	LT. STA.	441+88.40	TO	442+32.10
1	RT. STA.	441+87.20	TO	442+29.90
4	TOTAL			

66500105 WOVEN WIRE FENCE, 4'				
FOOT	LOCATION			REMARKS
207	LT. STA.	439+11.50	TO	441+23.90
247	LT. STA.	441+44.40	TO	444+00.00
454	TOTAL			

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT				
EACH	LOCATION			REMARKS
1	LT. STA.	435+75.70	TO	436+25.70
1	RT. STA.	435+70.10	TO	436+20.10
1	LT. STA.	444+22.00	TO	444+72.00
1	RT. STA.	443+16.30	TO	443+66.30
4	TOTAL			

FILE NAME = P:\CUBBEL WEST Projects\2009\8P-0147_IL173\Civil\Drawn\SH\0160129-811-2-08\sheet01.dgn



USER NAME = #USER#	DESIGNED - SBP/KMA	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 1/5/2011	CHECKED - PJF	REVISED -
	DATE - 12/14/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 10 OF 106 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	132 B-2	McHENRY	106	10
CONTRACT NO. 60129				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				