

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY 80% FED. 20% STATE		CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT		0005 QUANTITY		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	21	21		
25200110	SODDING, SALT TOLERANT	SQ YD	21	21		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	23	23		
40600300	AGGREGATE (PRIME COAT)	TON	112	112		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	84	84		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	965	965		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1199	1199		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4697	4697		
40600535	LEVELING BINDER (HAND METHOD), N70	TON	20	20		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	550	550		
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	350	350		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	54942	54942		
44000600	SIDEWALK REMOVAL	SQ FT	900	900		
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	5354	5354		
44200966	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	74	74		
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	20	20		
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	10	10		
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	260	260		
44201299	DOWEL BARS 1 1/2"	EACH	420	420		
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	354	354		
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	593	593		
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	351	351		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	3802	3802		
44213100	PAVEMENT FABRIC	SQ YD	250	250		
44213200	SAW CUTS	FOOT	1503	1503		
44213202	TIE BARS 1"	EACH	350	350		
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2		
60406520	FRAMES AND LIDS, OPEN LID (CITY OF CHICAGO)	EACH	5	5		
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2		
60406530	FRAMES AND LIDS, CLOSED LID (CITY OF CHICAGO)	EACH	5	5		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		

Δ = Non-participating
* SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY 80% FED. 20% STATE		CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT		0005 QUANTITY		
67100100	MOBILIZATION	L SUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3490	3490		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	3456	3456		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	36605	36605		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	19404	19404		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	3460	3460		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2714	2714		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	2708	2708		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	389	389		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1728	1728		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18303	18303		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	9702	9702		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1730	1730		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1357	1357		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1354	1354		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	825	825		
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2349	2349		
Δ X55 39700	STORM SEWERS TO BE CLEANED	FOOT	7500	7500		
X6020083	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	5	5		
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	129	129		
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	124	124		
Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	215	215		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	156	156		
* 78000200	POLYUREA PAVEMENT MARKING TYPE I-LETTERS AND SYMBOLS	SQ FT	82	82		
* 78000210	POLYUREA PAVEMENT MARKING TYPE I-LINE 4"	FOOT	900	900		
* 78000230	POLYUREA PAVEMENT MARKING TYPE I-LINE 6"	FOOT	677	677		
* 78000240	POLYUREA PAVEMENT MARKING TYPE I-LINE 8"	FOOT	240	240		
* 78000250	POLYUREA PAVEMENT MARKING TYPE I-LINE 12"	FOOT	75	75		
* 78000270	POLYUREA PAVEMENT MARKING TYPE I-LINE 24"	FOOT	144	144		
Z0040665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		

FILE NAME : P:\2009\ME09006_VerVar_Phil.CADD\W024_Cermak\Shets\04-DIBK86-sht-Cermak-S00.dgn
USER NAME : Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
630.705.8110 voice, 630.839.2566 fax
www.mps-ill.com

MILLENNIA PROFESSIONAL SERVICES

DESIGNED - CML	REVISED -
DRAWN - JGH	REVISED -
CHECKED - TVN	REVISED -
DATE - 02/09/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CERMAK ROAD
HALSTED ST. TO McCORMICK SQUARE

SUMMARY OF QUANTITIES

F.A.U. RTE. 1453	SECTION 2010-033- RS	COUNTY COOK	TOTAL SHEETS 23	SHEET NO. 4
CONTRACT NO. 60K86			Rev.	

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT

P:\2009\ME09006_VerVar_Phil.CADD\W024_Cermak\Shets\04-DIBK86-sht-Cermak-S00.dgn