


SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				0014 <i>URBAN</i>	
28100107	STONE RIPRAP, CLASS A4	SO YD	59	59	
28200200	FILTER FABRIC	SO YD	59	59	
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	26	26	
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	124	124	
40600300	AGGREGATE (PRIME COAT)	TON	3	3	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	75	75	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	138	138	
42001165	BRIDGE APPROACH PAVEMENT	SO YD	107	107	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	1,235	1,235	
50102400	CONCRETE REMOVAL	CU YD	36.2	36.2	
50104650	SLOPE WALL REMOVAL	SO YD	141	141	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	36.2	36.2	
50300260	BRIDGE DECK GROOVING	SO YD	37	37	
50300300	PROTECTIVE COAT	SO YD	2,715	2,715	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3,410	3,410	
50800505	<i>BAR SPICERS</i>	<i>EACH</i>	<i>106</i>	<i>106</i>	
51100100	SLOPE WALL 4 INCH	SO YD	141	141	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	176	176	
60018300	<i>CONCRETE MEDIAN SURFACE, 4 INCH</i>	<i>SQ FT</i>	<i>3,000</i>	<i>3,000</i>	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1.0	1.0	
70106800	<i>CHANGEABLE MESSAGE SIGN</i>	<i>CAL MO</i>	<i>4</i>	<i>4</i>	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	100	100	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2,543	2,543	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	36	36	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,531	4,531	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	75	75	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,152	1,152	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	11	11	
X4403800	<i>MEDIAN SURFACE REMOVAL</i>	<i>SQ FT</i>	<i>3,000</i>	<i>3,000</i>	
78300100	PAVEMENT MARKING REMOVAL	SO FT	2,081	2,081	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	11	11	
85000200	<i>MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION</i>	<i>EACH</i>	<i>2</i>	<i>2</i>	
X7010216	<i>TRAFFIC CONTROL AND PROTECTION, (SPECIAL)</i>	<i>L SUM</i>	<i>1.0</i>	<i>1.0</i>	
X7011015	<i>TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)</i>	<i>L SUM</i>	<i>1.0</i>	<i>1.0</i>	
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	7,629	7,629	
Z0004552	APPROACH SLAB REMOVAL	SO YD	107	107	
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	540	540	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	324	324	
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	132	132	
Z0016200	DECK SLAB REPAIR (PARTIAL)	SO YD	2	2	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				0014 <i>URBAN</i>	
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	77.1	77.1	
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2	2	

* SPECIALTY ITEMS

	USER NAME = 2planmd	DESIGNED - DJB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL ROUTE 68 (DUNDEE RD.) OVER IL ROUTE 53 SUMMARY OF QUANTITIES	F.A.P. RTE. 343	SECTION 531-4HBK-BR-1	COUNTY COOK	TOTAL SHEETS 25	SHEET NO. 3				
	PLOT SCALE = 50:00 ' / IN.	DRAWN - ENTRAN	CHECKED - TMH				REVISED -	SCALE: 50:00 ' / IN.	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			
	PLOT DATE = 2/28/2011	DATE - 02/18/11	REVISED -				REVISED -	CONTRACT NO. 60L47						
	Rev.													

FILE NAME = G:\project\2102155_0066A\CADD\Civil\Sheet\017010-031-S00.dgn