



Concrete Removal for Joint Reconstruction
(See Sheet S4) (typ.)

Limits of Protective Coat

IL Route 68
(Dundee Road)

** Approach Slab Removal, Bridge Approach Pavement
and Protective Coat. See Sheet S5 for details.

PLAN

BILL OF MATERIAL

Symbol	Item Description	Unit	Quantity
	Protective Coat	Sq. Yd.	2,608
	Structural Repair of Concrete (Depth equal to or less than 5 inches)	Sq. Ft.	250
	Deck Slab Repair (Partial)	Sq. Yd.	2
	HMA resurfacing. See Roadway Plans.		

FILE NAME = G:\p\sect\2102155.006\AV\CARD\Structure\0160961.60L47.003.Dock_Repair.dgn

	USER NAME = Zsagerb	DESIGNED - BHS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BRIDGE DECK & APPROACH SLAB RESURFACING PLAN S.N. 016-0961	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = N/A	CHECKED - GSP	REVISED -			343	531-4HBK-BR-1	COOK	25	13
	PLOT DATE = 2/28/2011	DRAWN - MJB	REVISED -			CONTRACT NO. 60L47				
					SHEET NO. S3 OF 11 SHEETS	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				