



SCHEDULE OF QUANTITIES

PAY ITEM	UNIT	QUANTITY
CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	387
CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	113
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	387
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2
DRILL EXISTING HANDHOLE	EACH	2
TRANSCIEVER-FIBER OPTIC	EACH	1
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2340
REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	490
REMOVE EXISTING HANDHOLE	EACH	1
ELECTRIC CABLE IN CONDUIT, TRACER NO. 14 1C	FOOT	1170
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	1170



NOTE:
THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

PREPARED BY:
CEMCON, Ltd.
Consulting Engineers, Land Surveyors & Planners
2280 White Oak Circle, Suite 100
Aurora, Illinois 60504-9675
Ph: 630.862.2100 Fax: 630.862.2199
E-Mail: oadd@cemcon.com Website: www.cemcon.com

FILE NAME = MICROST\352887\SCHEMATIC.DGN	USER NAME = RDS	DESIGNED - KK	REVISED -
	PLOT SCALE = 1"=20'	DRAWN - JGC	REVISED -
	PLOT DATE = 1-13-11	CHECKED - BPT	REVISED -
		DATE - 2-3-11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERCONNECT SCHEMATIC
U.S. ROUTE 12 (RAND ROAD) AT HONEY LAKE ROAD

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	SY-2-N	LAKE	34	18
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60L68	