

80% FED.  
20% STATE

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0005 QUANTITY	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	62	62	
40600300	AGGREGATE (PRIME COAT)	TON	488	488	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	18	18	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1,401	1,401	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1,034	1,034	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	8,175	8,175	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	81,235	81,235	
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3,373	3,373	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	4,494	4,494	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	48	48	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	504	504	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	728	728	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	2,178	2,178	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	28	28	
60406000	FRAMES AND LIDS, TYPE I, OPEN LID	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	24,600	24,600	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	4,374	4,374	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	43,628	43,628	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	19,828	19,828	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	4,104	4,104	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,044	2,044	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3,764	3,764	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1,640	1,640	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2,127	2,127	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21,833	21,833	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	9,840	9,840	
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2,052	2,052	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,022	1,022	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,882	1,882	
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SO FT	183	183	

\* INDICATES SPECIALTY ITEM

80% FED.  
20% STATE

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0005 QUANTITY	
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	48	48	
88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,820	1,820	
Z0018500	DRAINAGE STRUCTURE TO BE CLEANED	EACH	104	104	
Z0076600	TRAINEES	HOUR	500	500	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
Z0030050	TEMPORARY INFORMATION SIGNING	SO FT	52	52	
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.75, N50	TON	3,504	3,504	
X5539700	STORM SEWERS TO BE CLEANED	FOOT	4,056	4,056	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	249	249	
XX005972	STAMPED ASPHALT CROSSWALK	SO YD	498	498	
Z0048900	RAILROAD TRACK REMOVAL	FOOT	125	125	

\* INDICATES SPECIALTY ITEM  
Δ = Non-participating

COPYRIGHT © 2011 BY BAXTER & WOODMAN, INC.  
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM  
 LICENSE NO. 018-00023 - EXPIRES 02/28/2011  
 4888888  
 ...:\p1015\00083\wo13\en101  
 ...:\p1015\00083\wo13\en101  
 ...:\p1015\00083\wo13\en101  
 ...:\p1015\00083\wo13\en101



DESIGNED - CAC	REVISED - PER IDOT 2-3-11
DRAWN - BCD	REVISED -
CHECKED - RWL	REVISED -
DATE - 12-17-10	FILE - 100153-wo13-soq.sht

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

NORTH AVENUE  
MILWAUKEE AVENUE TO CLARK STREET  
SUMMARY OF QUANTITIES

F.A.P. RTE. 307	SECTION 2010-140-RS	COUNTY COOK	TOTAL SHEETS 29	SHEET NO. 3
CONTRACT NO. 60N19				
FED. ROAD DIST. NO. 1   ILLINOIS   FED. AID PROJECT				

SCALE: NONE STA. TO STA.