

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SAFETY IMPROVEMENTS	
				100% FED 0% VILLAGE	0021
20101000	TEMPORARY FENCE	FOOT	335	335	
20101200	TREE ROOT PRUNING	EACH	25	25	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	367	367	
20400800	FURNISHED EXCAVATION	CU YD	15	15	
20800150	TRENCH BACKFILL	CU YD	22	22	
28000400	PERIMETER EROSION BARRIER	FOOT	480	480	
28000500	INLET AND PIPE PROTECTION	EACH	6	6	
28000510	INLET FILTERS	EACH	4	4	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200	200	
42001300	PROTECTIVE COAT	SQ YD	1,072	1,072	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	9,603	9,603	
42400800	DETECTABLE WARNINGS	SQ FT	32	32	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	436	436	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	15	15	
44000600	SIDEWALK REMOVAL	SQ FT	100	100	
44201670	CLASS D PATCHES, TYPE I, 2 INCH	SQ YD	3	3	
50901760	PIPE HANDRAIL	FOOT	115	115	
54215547	METAL END SECTIONS 12"	EACH	3	3	
54215550	METAL END SECTIONS 15"	EACH	2	2	
550B0050	STORM SEWERS, CLASS B, TYPE 112"	FOOT	145	145	
550B0070	STORM SEWERS, CLASS B, TYPE 115"	FOOT	25	25	
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	2	2	
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	1	1	
60236200	INLETS, TYPE A, TYPE B GRATE	EACH	1	1	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	
60258100	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	2	2	
60600605	CONCRETE CURB, TYPE B	FOOT	10	10	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	15	15	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	96	96	
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	120	120	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	4	4	
Z0066500	STABILIZED DRIVEWAYS 7"	SQ YD	316	316	
X2500900	SEEDING, CLASS 1 (SPECIAL)	ACRE	0.9	0.9	
XX001877	SUMP PUMP LINE CONNECTION	EACH	1	1	
XX007761	BUFFALO BOX ADJUSTMENT, SPECIAL	EACH	2	2	

LEGEND
 - DENOTES SPECIALTY ITEM

JJB JAMES J. BENES & ASSOCIATES, INC.
 950 Warrenville Road, Suite 101, Lisle, Illinois 60532
 Tel. (630) 719-7570 • Fax (630) 719-7589

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00056-00-SW	DuPAGE	26	3
CONTRACT NO. 63537			ILLINOIS FED. AID PROJECT	

FILE NAME =	USER NAME =	DESIGNED -- BDH	REVISED --
		DRAWN -- SMP	REVISED --
PLOT SCALE =	CHECKED -- BDH	REVISED --	
PLOT DATE =	DATE -- 9-29-10	REVISED --	

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 DEVON AVENUE AND SCHIESHER ELEMENTARY SCHOOL

SCALE: NONE SHEET NO. 3 OF 26 SHEETS STA. _____ TO STA. _____