

PAY ITEM #	ITEM	UNIT	0021 TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	260
20800150	TRENCH BACKFILL	CU YD	185
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1000
25000100	SEEDING, CLASS 1	ACRE	0.02
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2
25100630	EROSION CONTROL BLANKET	SQ YD	1000
25200200	SUPPLEMENTAL WATERING	UNIT	15
28000305	TEMPORARY DITCH CHECKS	FOOT	50
28000400	PERIMETER EROSION BARRIER	FOOT	1200
28000510	INLET FILTERS	EACH	12
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	130
35300310	PORTLAND CEMENT CONCRETE BASE COURSE 8 1/2"	SQ YD	150
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	15
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	185
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	8100
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	390
42400800	DETECTABLE WARNINGS	SQ FT	60
44000100	PAVEMENT REMOVAL	SQ YD	150
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	150
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	25

PAY ITEM #	ITEM	UNIT	0021 TOTAL QUANTITY
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	3
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	150
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	222
56400100	FIRE HYDRANTS TO BE MOVED	EACH	2
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	2
60207005	CATCH BASINS, TYPE C, TYPE 1 FRAME, CLOSED LID	EACH	1
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	2
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1
60255500	MANHOLES TO BE ADJUSTED	EACH	2
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1300
61140100	STORM SEWERS (SPECIAL), 10"	FOOT	30
61140200	STORM SEWERS (SPECIAL), 12"	FOOT	20
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1

* SPECIAL PROVISION

EARTHWORK SCHEDULE

Street	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL PLACEMENT
80th Ave	CY 306	CY 260	CY 215	CY 45	CY 110

FILE NAME = N:\palospark\100055\Civil\NS001_100055.DGN	USER NAME = CMCCOLLO	DESIGNED - CJM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES AND EARTHWORK TABLE VILLAGE OF PALOS PARK	F.A.U. RTE. 2756	SECTION 09-00029-00-SW	COUNTY COOK	TOTAL SHEETS 14	SHEET NO. 3
PLOT SCALE = 1"	CHECKED - KRC/DV	REVISED -	SCALE: 1:1'			SHEET NO. OF SHEETS STA. TO STA.	CONTRACT NO. 63548			
PLOT DATE = 2/17/2011	DATE - 10/20/10	REVISED -	ILLINOIS FED. AID PROJECT							