


EARTHWORK SCHEDULE						
STATION	20200100		20201200		EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL			
LINE "DUNHAM"	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
104+50 TO 105+00	15	13	3	0	13	
105+00 TO 105+50	100	85	26	5	80	
105+50 TO 106+00	178	151	46	11	141	
106+00 TO 106+50	353	300	85	70	231	
106+50 TO 107+00	518	440	125	141	300	
107+00 TO 107+50	452	384	124	183	201	
107+50 TO 108+00	366	311	122	255	56	
108+00 TO 108+50	331	281	117	317	-36	
108+50 TO 109+00	373	317	117	350	-32	
109+00 TO 109+50	385	327	115	352	-24	
109+50 TO 110+00	330	281	151	489	-208	
110+00 TO 110+50	31	27	34	118	-92	
110+50 TO 111+00	110	93	85	283	-190	
111+00 TO 111+50	120	102	87	285	-183	
111+50 TO 112+00	81	69	81	265	-196	
112+00 TO 112+50	58	49	73	218	-169	
112+50 TO 113+00	65	56	69	178	-123	
113+00 TO 113+50	87	74	72	133	-59	
113+50 TO 114+00	143	122	71	85	37	
114+00 TO 114+40	94	80	35	29	51	
PGE			50			
TOTALS	4,190	3,562	1,688	3,767	-205	

EARTHWORK SCHEDULE			
LOCATION FROM CENTERLINE			20300100
			CHANNEL EXCAVATION
			(CU YD)
61' RT TO 48' RT			5
48' RT TO 36' RT			13
36' RT TO 20' RT			30
20' RT TO 13' RT			16
13' RT TO 13' LT			46
13' LT TO 20' LT			11
20' LT TO 30' LT			9
30' LT TO 51' LT			10
51' LT TO 73' LT			11
TOTALS			151

SUMMARY			
20200100	20400800	20201201	20201201
EARTH EXCAVATION	FURNISHED EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CHANNEL EXCAVATION
(CU YD)	(CU YD)	(CU YD)	(CU YD)
4,190	205	1,688	151

FILE NAME = n:\p\0\3381\3381.dwg\design\proposed\3381\02-04_00r-thach.dgn

 Ciorba Group, Inc. CONSULTING ENGINEERS 5507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60656 Tel. 773.775.4009 Fax 773.775.4014	USER NAME = espino PLOT SCALE = 1:8000 / IN. PLOT DATE = 2/4/2011	DESIGNED - DKD DRAWN - DKD CHECKED - CLG DATE - 02/07/2011	REVISED - REVISED - REVISED - REVISED -	MCHENRY COUNTY DIVISION OF TRANSPORTATION	EARTHWORK SCHEDULES	TR RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.	07-00340-00-BR MCHENRY 46 5	CONTRACT NO. 63552
	SCALE: N.T.S.	SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					