

SUMMARY OF QUANTITIES

SI	CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY	71st STREET BRIDGE SN 016-7721	RETAINING WALLS SN 016-7722 THRU SN 016-7726	TRAINEES	71st STREET PUMPING STATION
					0004	0008	0040	0042	0043
	Z0018911	DRILL AND GROUT #6 TIE BARS	EACH	52	52				
	Z0022800	FENCE REMOVAL	FOOT	1,569	1,362				207
	Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1				
	Z0026404	FURNISHING SOLDIER PILES (W SECTION)	FOOT	7,361	0		7361		
	Z0030275	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 2	EACH	2	2				
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	379	379				
	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	100	100				
	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	1,879	0	177	1,702		
*	Z0047700	PUMPING STATION	L SUM	1	1				
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
*	Z0048900	RAILROAD TRACK REMOVAL	FOOT	28	28				
	Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	231	231				
	Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	76	76				
	Z0062456	TEMPORARY PAVEMENT	SQ YD	800	800				
	Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	450	0	450			
	Z0076600	TRAINEES	HOUR	2,000	0			2,000	
*	XX008495	STORM SEWER JACKED IN PLACE 84" (SPECIAL)	FOOT	128	128				
*	XX008497	CHECK VALVE 12"	EACH	3	0				3
*	XX008498	CARBON STEEL FORCE MAIN, 12"	FOOT	60	0				60
*	XX008499	8" VALVE IN 48" DIA. VALVE VAULT, TYPE 1 FRAME, CLOSED LID	EACH	3	3				
*	XX008500	8" VALVE IN VALVE BOX	EACH	1	1				
*	XX008501	16" VALVE IN VALVE BOX	EACH	1	1				
*	XX008502	16"X8" REDUCING TAPPING SLEEVE AND 8" DIA. GATE VALVE IN 6 FT-DIA. VALVE VAULT, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
	XX008503	CONSTRUCTION OF JUMP SPANS	L SUM	1	0	1			
	XX008525	PRECAST CONCRETE BACKWALLS	CU YD	67	0	67			
*	81603598	UNIT DUCT, 600V, 6-1/C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1 1/2" POLYETHYLENE	FOOT	1,525	1,525				
	X5500320	PRECAST TRANSITION PIPE, 36" TO 84" DIAMETER STORM SEWER	EACH	1	1				
	X5500330	PRECAST TRANSITION PIPE, 78" TO 84" DIAMETER STORM SEWER	EACH	1	1				
	XX008504	PRECAST "T" MANHOLES FOR 78" DIAMETER STORM SEWER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
	XX008505	PRECAST "T" MANHOLES FOR 84" DIAMETER STORM SEWER, TYPE 1 FRAME, CLOSED LID	EACH	3	3				

* DENOTES SPECIALTY ITEM

FILE NAME = P:\60195677\000_CAD\001_Drawing\Sheets\Civil\80195677-sht-500-06.dgn



USER NAME = merry	DESIGNED - NJH	REVISED -
PLT SCALE = 1:000' / 1"	DRAWN - NJH	REVISED -
PLT DATE = 3/16/2011	CHECKED - TJW	REVISED -
	DATE - March 17, 2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 6 OF 6 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1537	06-00050-00-GS	COOK	209	9
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CRE-900317091			CONTRACT NO. 63556	