

SUMMARY OF QUANTITIES

LOCATION OF WORK				DIVERSEY AVE. DERROUGH AVE. RHODES AVE. 100% FED	DERROUGH AVE. 100% LOCAL	PROJECT TOTAL
FUNDING SOURCE				SRTS	LOCAL	TOTAL
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
ITEM #	ITEM	UNIT	0021	0004		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6	0	6	
20101100	TREE TRUNK PROTECTION	EACH	1	0	1	
20101200	TREE ROOT PRUNING	EACH	3	0	3	
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	40.5	4.5	45	
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	40.5	4.5	45	
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	40.5	4.5	45	
20101700	SUPPLEMENTAL WATERING	UNIT	9	1	10	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	20	60	80	
20400800	FURNISHED EXCAVATION	CU YD	25	0	25	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	20	60	80	
20800150	TRENCH BACKFILL	CU YD	50	0	50	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	120	490	610	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	800	100	900	
25000100	SEEDING, CLASS 1	ACRE	0.45	0.05	0.5	
25100530	EROSION CONTROL BLANKET	SQ YD	1460	65	1525	
28000500	INLET AND PIPE PROTECTION	EACH	6	0	6	
28000510	INLET FILTERS	EACH	20	1	21	
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	95	10	105	
35101598	AGGREGATE BASE COURSE, TYPE B 3"	SQ YD	70	0	70	
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	100	45	145	
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	120	490	610	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	55	15	70	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	40	55	95	
40600300	AGGREGATE (PRIME COAT)	TON	1	2	3	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	50	120	170	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	85	55	140	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	70	0	70	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	8100	0	8100	
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	475	0	475	
42400800	DETECTABLE WARNINGS	SQ FT	60	0	60	
44000100	PAVEMENT REMOVAL	SQ YD	775	360	1135	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	290	40	330	
44000300	CURB REMOVAL	FOOT	45	0	45	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	380	0	380	
44000600	SIDEWALK REMOVAL	SQ FT	325	0	325	
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	0	50	50	
54213689	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	6	0	6	
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	6	0	6	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	187	0	187	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	40	0	40	
55100500	STORM SEWER REMOVAL 12"	FOOT	153	0	153	
55101200	STORM SEWER REMOVAL 24"	FOOT	5	0	5	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	100	0	100	
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	4	0	4	
60200905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	7	0	7	
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1	2	
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	0	2	
60903800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6, 12	FOOT	1200	0	1200	
67100100	MOBILIZATION	L SUM	0.9	0.1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701305	L SUM	0.9	0.1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	0.9	0.1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	0.9	0.1	1	
72000100	SIGN PANEL - TYPE 1	SQ FT	32	0	32	
72900100	METAL POST - TYPE A	FOOT	70	0	70	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	26	0	26	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	30	0	30	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	34	0	34	
* 81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	1	0	1	
- 89502380	REMOVE EXISTING HANDHOLE	EACH	1	0	1	
X 4810200	AGGREGATE SHOULDER REMOVAL	CU YD	260	55	315	
- X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	3	0	3	
- X6961700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL)	FOOT	250	345	595	
* 20013798	CONSTRUCTION LAYOUT	L SUM	0.9	0.1	1	
- 20016400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	2	0	2	
- 20018700	DRAINAGE STRUCTURES TO BE REMOVED	EACH	5	0	5	
- 20056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	5	0	5	

- INDICATES SPECIAL PROVISION
* INDICATES SPECIALTY ITEM

FILE NAME =
N:\NORTH LAKE\940832DC107\Civil\equal.dwg

USER NAME = EDTODA
PLOT SCALE = N.T.S.
PLOT DATE = 2/8/2011

DESIGNED - AMP
DRAWN - EDT
CHECKED - MEW
DATE - 02/08/11

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. OF SHEETS STA. 10+00.00 TO STA. 24+92.22

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
----	10-00074-00-SW	COOK	22	3
CONTRACT NO. 63559			ILLINOIS FED. AID PROJECT	