

# INDEX OF SHEETS

1. Cover Sheet
2. Index of Sheets, Standards, General Notes
3. Summary of Quantities
4. Traffic Control Plan Stage I
5. Traffic Control Plan Stage II
6. 'To Activate Signal' Sign Detail

## Bridge Plans

7. General Plan & Elevation
8. 33" x 36" PPC Deck Beam
9. 33" x 36" PPC Deck Beam Details
10. Repair Details
11. Repair Details
- 11A. Traffic Barrier Terminal Details
12. Right-of-Way Plat

# STANDARDS

- 701006-03 Off-Road Operations, 2L, 2W, 15 5/32 (4.5 m) to 24" (600 mm) From Pavement Edge
- 701301-04 Lane Closure, 2L, 2W, Short Time Operations
- 701311-03 Lane Closure, 2L, 2W, Moving Operations - Day Only
- 701321-11 Lane Closure, 2L, 2W, Bridge Repair with Barrier
- 701901-01 Traffic Control Devices
- 704001-06 Temporary Concrete Barrier
- 720011-01 Metal Posts for Signs, Markers and Delineators
- 728001-01 Telescoping Steel Sign Support
- 729001-01 Applications of Types A and B Metal Posts (For Signs & Markers)

# GENERAL NOTES

The final top four inches of soil in any right-of-way area disturbed by the Contractor must be capable of supporting vegetation. The soil must be from the A horizon (zero to 2' deep) of soil profiles of local soils.

All Borrow/Waste/Use sites must be approved by the Department prior to removing any material from the project or initiating any earthmoving activities, including temporary stockpiling outside the limits of construction.

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per Cubic Yard for CONCRETE REMOVAL.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of CONCRETE REMOVAL.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the CONCRETE REMOVAL.

At bridge expansion joints, if temporary expansion joint bulkheads are attached to adjacent deck slabs or abutments for support, the Contractor shall cut the attachments as soon as the concrete has set to prevent joint damage due to horizontal contraction or expansion.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123.

FILE NAME =	USER NAME = linkdj	DESIGNED -	REVIS	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>General Notes, Index of Sheets Standards</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
D:\BR\CADD plans\Jo Daviess County\043004\PLANeng.dgn	DRAWN -	REVIS	642			(10BR-3)M	JODAVIESS	12	2		
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVIS	CONTRACT NO. 64C90								
PLOT DATE = Sat Jan 22 08:46:56 2011	DATE -	REVIS	[ILLINOIS] FED. AID PROJECT								
						SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____			

Rev.