



GENERAL NOTES:

1. FOR ELECTRICAL GENERAL NOTES, SYMBOLS LEGEND AND ABBREVIATIONS REFER TO SHEET LI-1.
2. PROVIDE TEMPORARY LIGHTING UNIT NEAR EXIT/ENTRANCE OF RAMPS AND CROSSOVERS FOR CONSTRUCTION PHASES.
3. CONNECT TEMPORARY LIGHTING UNITS TO EXISTING LIGHTING SYSTEM.
4. MAINTAIN EXISTING LIGHTING CONTROLLER AND EXISTING LIGHTING UNITS AS SHOWN FOR TEMPORARY LIGHTING. EXISTING LIGHTING UNITS AND CONTROLLER TO BE REMOVED AFTER THE PROPOSED LIGHTING SYSTEM IS INSTALLED AND OPERATIONAL. REMOVE EXISTING BRANCH BREAKERS. ADD (3) 30A/2P BRANCH BREAKER IN THE EXISTING CONTROLLER FOR TEMPORARY LIGHTING UNITS. THE COST OF THIS SHALL BE INCLUDED IN PAY ITEM "MAINTENANCE OF TEMPORARY LIGHTING SYSTEM". NO SEPARATE PAYMENT WILL BE MADE FOR THIS.
5. REMOVE THE TEMPORARY LIGHTING UNITS AFTER THE PROPOSED LIGHTING SYSTEM IS INSTALLED AND OPERATIONAL.
6. ALL SALVAGE MATERIALS SHALL BE DELIVERED TO IDOT DISTRICT 3 STORAGE FACILITIES.
7. PROVIDE TWO SETS OF AERIAL CABLES FOR TEMPORARY LIGHTS.
8. AFTER PROPOSED LIGHTING IS INSTALLED AND START FUNCTIONING, REMOVE TEMPORARY 60 FOOT CLASS 4 WOOD POLE. THE COST OF ITS REMOVAL SHALL BE INCLUDED IN THE PAY ITEM "REMOVAL OF TEMPORARY LIGHTING UNIT." (TYP.)
9. MAINTAIN UNDERGROUND FEED.

Delta Engineering, Inc.
 CONSULTING ENGINEERS, CONSTRUCTION MANAGERS, SUPERVISORS
 111 West Jackson Blvd., Suite 910 Chicago, IL 60604-2001

FILE NAME = g9\zd40403\LI-7.DGN	USER NAME = kkhon	DESIGNED - HS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TEMPORARY LIGHTING PLAN I-57 AND IL ROUTE 50	F.A.J. RTE. 57	SECTION (46-2) I, HBR, VBR	COUNTY KANKAKEE	TOTAL SHEETS 558	SHEET NO. 254	
PLOT SCALE = 1:500					SCALE: SHEET NO. OF SHEETS STA. TO STA.		FED. ROAD DIST. NO. 3 (ILLINOIS) FED. AID PROJECT				
PLOT DATE = 12/17/2010					DATE = 12-17-2010		CONTRACT NO. 66409				