

SIDEWALK SCHEDULE FOR NEW RAMP INSTALLATION									
LOCATION SIDESTREET	PCC SIDEWALK 4"	DETECTABLE WARNINGS	CC&G (SPEC)	SIDEWALK REMOVAL	CC&G REMOV (SPEC)	SOD, SALT TOLERANT	SUPPLEMNTAL WATERING	EARTH EXCAV	FURNISH EXCAV
QUAD	SO FT	SO FT	FOOT	SO FT	FOOT	SO YD	UNIT	CU YD	CU YD
LASALLE COUNTY									
LAFAYETTE ST									
SW	30	8	10	30	10				
NW	8	8		8					
SE	8	8		8					
NE	8	8		8					
CREVE COUER ST									
SW	40	8	12	40	12				
NW	8	8		8					
SE	30	8	10	30	10				
NE	100	8	18	100	18				
CHARTRES ST									
SW	8	8		8					
NW	8	8		8					
SE	8	8		8					
NE	8	8		8					
PERU ST									
NW	110	8	18	110	18				
NE	30	8		30					
ORLEANS ST									
SW	50	8	14	50	14	3.1	0.03		
NW	100	8	18	100	18	4	0.04		
SE	60	8	20	60	20	3.6	0.03		
NE	110	8	18	110	18	4	0.04		
ST LOUIS ST									
SW	42	8	9	42	9				
NW	100	8	18	100	18				
NE	100	8	18	100	18	4	0.04		
BUFFALO ST									
SW	100	8	18	100	18	4	0.04		
NW	16	16		16					
SE	126	8	18	126	18	4.5	0.04	0.3	0.1
NE	100	8	18	100	18	4	0.04		
SW	100	8	20	100	20	2.7	0.02		
NW	100	8	16	100	16				
SE	65	8	16	65	16	2.7	0.02		
NE	16	16		16					
PULASKI ST									
SW	40	8	10	40	10				
NW	125	8	22	125	22				
SE	100	8	14	100	14	3.3	0.03		
NE	160	8	26	160	26				
PROSPECT AVE									
SW	100	8	18	100	18	4	0.04		
NW	100	8	14	100	14				
SE	100	8	18	100	18				
NE	85	8	15	85	15	2.7	0.02		
PINE ST									
SW	50	8	16	50	16	3.2	0.03		
NW	100	8	18	100	18	4	0.04		
SE	70	8	14	70	14	3.2	0.03		
NE	100	8	18	100	18	4	0.04		
FARM ST									
SW	8	8		8					
SE	70	8	20	85	20	3.2	0.03		
MONKS AVE									
NW	100	8	18	100	18				
NE	100	8	18	100	18				
ROCK ST									
SW	100	8	18	100	18	4	0.04		
NW	100	8	18	100	18				
SE	100	8	18	100	18				
NE	100	8	18	100	18	4	0.04		
PLUM ST									
SW	100	8	18	100	18	4	0.04		
NW	100	8	18	100	18	4	0.04		
SE	50	8	20	50	20	3.2	0.03		
NE	80	8	15	80	15	3.8	0.03		
SUBTOTAL	3727	440	691	3742	691	87.2	0.7848	0.3	0.1