

SUMMARY OF QUANTITIES

CONT. MAINT

100% STATE 0014
HENDERSON

CODE NO.	ITEM	UNIT	RURAL	TOTAL
40603540	POLYMERIZED SURFACE COURSE, MIX "D", N70 <i>HOT-MIX ASPHALT</i>	TON	1.4	1.4
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQFT	129	129
58100200	WATERPROOFING MEMBRANE SYSTEM	SQYD	17.1	17.1
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	43	43
67100100	MOBILIZATION	LSUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	LSUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	727	727
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQFT	242	242

FILE NAME = SN 036-0003 US34ovr01dTomCrk.dgn

USER NAME = corpdm
PLOT SCALE = 100.0000' / IN.
PLOT DATE = 2/4/2011

DESIGNED - D CORP	REVISED - -----
DRAWN - D CORP	REVISED - -----
CHECKED - C JONES	REVISED - -----
DATE - 2/03/2011	REVISED - -----

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: ----- SHEET NO. 3 OF 9 SHEETS STA. 625+30.00 TO STA. 625+73.00

F.A.P. RTE. 313	SECTION (6BR)1	COUNTY HENDERSON	TOTAL SHEETS 3	SHEET NO. 9
PPC BEAM REPL.		CONTRACT NO. 68A17		
ILLINOIS FED. AID PROJECT				