

## INDEX OF SHEETS

| SHEET NO. | DESCRIPTION   |
|-----------|---|
| 1         | COVER SHEET   |
| 2         | INDEX OF SHEETS   |
| 2         | LIST OF STANDARDS   |
| 2         | GENERAL NOTES   |
| 3         | SUMMARY OF QUANTITIES   |
| 4         | GENERAL PLAN  |
| 5         | AS-BUILT PATCHING PLAN  |
| 6         | JOINT AND DRAIN REPAIR DETAILS  |
| 7         | PLAN AND ELEVATION FOR STRUCTURAL STEEL REPAIR                            |
| 8         | BEAM STRAIGHTENING DETAILS  |
| 9         | BEARING REPLACEMENT DETAILS   |
| 10-13     | AS-BUILT STRUCTURE PLANS - FOR INFORMATION ONLY                           |
| 14        | TRAFFIC CONTROL & PROTECTION DEVICES<br>(ROAD & SIDEROAD/STREET CLOSURES) |

## GENERAL NOTES

### GENERAL NOTES

#### G.N.-100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

#### G.N.-501A

THE EXISTING STRUCTURAL STEEL COATING CONTAINS LEAD. THE CONTRACTOR SHOULD FOLLOW THE GUIDE BRIDGE SPECIAL PROVISIONS FOR CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES TO DEAL WITH THE PRESENCE OF LEAD ON THIS PROJECT.

IT IS THE INTENT, WHEN REPLACING BRIDGE BEARINGS, TO NOT ONLY PROVIDE NEW AND PROPER SUPPORT FOR THE SUPERSTRUCTURE, BUT ALSO TO RE-ESTABLISH THE ORIGINAL DECK ELEVATIONS. SUPERSTRUCTURES THAT ARE HEAVED WITH PACK RUST SHALL BE ACCOUNTED FOR WHEN VERIFYING THE NECESSARY DIMENSIONS OF THE STEEL EXTENSIONS. THE AMOUNT OF HEAVE MEASURED AT EACH BEAM LINE SHALL BE SUBTRACTED FROM THE EXISTING BEAM-TO-BEARING SEAT CLEARANCE MEASURED BELOW THUS ENSURING THAT THE FINAL DECK ELEVATIONS WILL PROVIDE A FLUSH JOINT.

## LIST OF HIGHWAY STANDARDS

| STANDARD NO. | DESCRIPTION  |
|--------------|--|
| 000001-06    | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS                                 |
| 001006       | DECIMAL OF AN INCH AND OF A FOOT   |
| 701101-02    | OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5m) TO 24" (600mm) FROM PAVEMENT EDGE |
| 701106-02    | OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' (4.5m) AWAY                    |
| 701400-05    | APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY                                 |
| 701406-06    | LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY                        |
| 701901-01    | TRAFFIC CONTROL DEVICES  |

|  |                             |                |           |   |   |   |                  |           |                 |              |
|--|-----------------------------|----------------|-----------|---|---|---|------------------|-----------|-----------------|--------------|
| FILE NAME =  | USER NAME = simsgm          | DESIGNED - GMS | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>INDEX OF SHEETS,<br/>LIST OF STANDARDS &amp; GENERAL NOTES</b> | F.A.I.<br>RTE.  | SECTION          | COUNTY    | TOTAL<br>SHEETS | SHEET<br>NO. |
| c:\pwwork\pwwork\simsgm\d0184265\0570895-Bridge Repair Plans.dgn | PLOT SCALE = 40,0001' / IN. | DRAWN - GMS    | REVISED - |   |   | 72  | (10-71HB)BDR,BJR | CHAMPAIGN | 14              | 2            |
| PLOT DATE = 1/21/2011  | DATE = 01-20-2011           | CHECKED -      | REVISED - |   |   | CONTRACT NO. 70865<br>FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT |                  |           |                 |              |