

SUMMARY OF QUANTITIES

| CODE NO | ITEM | UNIT | LOCATION OF WORK: | | | | | | |
|-------------------------|---|-------|-------------------|---|--|--|---|---|--|
| | | | URBAN | FAP 804 U.S. 150 & University Ave. | FAP 804 U.S. 150 & Church St. | INTERCONNECT U.S. 150 & University Ave. | INTERCONNECT U.S. 150 & Church St. | FAP 804 U.S. 150 & University Ave. | FAP 804 U.S. 150 & Church St. |
| CONSTRUCTION TYPE CODE: | | | URBAN | 100% State 0021 | 100% State 0021 | 100% State 0021 | 100% State 0021 | 100% City 0021 | 100% City 0021 |
| | | | TOTAL QUANTITY | QUANTITY | QUANTITY | QUANTITY | QUANTITY | QUANTITY | QUANTITY |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 475.0 | 173.0 | 302.0 | | | | |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 478.0 | 171.0 | 307.0 | | | | |
| 67100100 | MOBILIZATION | L SUM | 1.0 | .5 | .5 | | | | |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1.0 | .5 | .5 | | | | |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1.0 | .5 | .5 | | | | |
| 81012300 | CONDUIT IN TRENCH, 1" DIA., PVC | FOOT | 88.0 | 48.0 | 40.0 | | | | |
| 81012600 | CONDUIT IN TRENCH, 2" DIA., PVC | FOOT | 118.0 | 44.0 | 74.0 | | | | |
| 81012700 | CONDUIT IN TRENCH, 2 1/2" DIA., PVC | FOOT | 84.0 | 20.0 | 64.0 | | | | |
| 81012800 | CONDUIT IN TRENCH, 3" DIA., PVC | FOOT | 73.0 | 39.0 | 34.0 | | | | |
| 81013000 | CONDUIT IN TRENCH, 4" DIA., PVC | FOOT | 17.0 | 17.0 | | | | | |
| 81013100 | CONDUIT IN TRENCH, 5" DIA., PVC | FOOT | 8.0 | | 8.0 | | | | |
| 81021330 | CONDUIT PUSHED, 2" DIA., PVC | FOOT | 771.0 | 74.0 | 53.0 | 386.0 | 258.0 | | |
| 81021340 | CONDUIT PUSHED, 2 1/2" DIA., PVC | FOOT | 23.0 | 23.0 | | | | | |
| 81021350 | CONDUIT PUSHED, 3" DIA., PVC | FOOT | 297.0 | 117.0 | 180.0 | | | | |
| 81021370 | CONDUIT PUSHED, 4" DIA., PVC | FOOT | 57.0 | 57.0 | | | | | |
| 81400100 | HANDHOLE | EACH | 10.0 | 5.0 | 4.0 | 1.0 | | | |
| 81400300 | DOUBLE HANDHOLE | EACH | 2.0 | 1.0 | 1.0 | | | | |
| 81702100 | ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12 | FOOT | 778.0 | | | 493.0 | 285.0 | | |
| 81702110 | ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10 | FOOT | 995.0 | | | | | 497.0 | 498.0 |
| 81900200 | TRENCH AND BACKFILL FOR ELECTRICAL WORK | FOOT | 388.0 | 168.0 | 220.0 | | | | |
| 82102250 | LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT | EACH | 4.0 | | | | | 2.0 | 2.0 |
| 85700200 | FULL-ACTUATED CONTROLLER AND TYPE IV CABINET | EACH | 2.0 | 1.0 | 1.0 | | | | |
| 86200200 | UNINTERRUPTABLE POWER SUPPLY, STANDARD | EACH | 2.0 | 1.0 | 1.0 | | | | |
| 86400100 | TRANSCEIVER - FIBER OPTIC | EACH | 2.0 | | | 1.0 | 1.0 | | |

| | | | | | | | | | | |
|--|---------------------------------|------------|-----------|---|---------------------------|---------------------|-----------|---------|--------------------|--------------|
| FILE NAME = | USER NAME = biggard | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| ct:\pw_work\pwidot\biggard\d0212155\7087 | Prospect Ave topo - signals.dgn | DRAWN - | REVISED - | | 804 | (13X-1, 14)TS | CHAMPAIGN | 13 | 3 | |
| | PLOT SCALE = 20,0000' / 1" IN. | CHECKED - | REVISED - | | SCALE: | SHEET NO. OF SHEETS | STA. | TO STA. | CONTRACT NO. 70879 | |
| | PLOT DATE = 1/31/2011 | DATE - | REVISED - | | ILLINOIS FED. AID PROJECT | | | | | |