

SUMMARY OF QUANTITIES

LOCATION OF WORK:

LOCATION #2
LOCATION #3
LOCATION #4
LOCATION #6
LOCATION #7

LOCATION #1	LOCATION #5	LOCATION #3	LOCATION #6	LOCATION #7
URBAN	RURAL	URBAN	RURAL	RURAL
100% STATE	100% STATE	100% STATE	100% STATE	100% STATE
ROUT & SEAL	ROUT & SEAL	ROUT & SEAL	ROUT & SEAL	ROUT & SEAL
DEWITT CO.	DEWITT CO.	MCLEAN CO.	MCLEAN CO.	PIATT CO.
0005	0005	0005	0005	0005

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
45100100	CRACK ROUTING (PAVEMENT)	FOOT	544,980.0	30,853.0	162,186.0	25,838.0	222,335.0	103,768.0
45100200	CRACK FILLING	POUND	218,445.0	12,341.0	65,329.0	10,335.0	88,933.0	41,507.0
67100100	MOBILIZATION	L SUM	1.0	0.10	0.10	0.10	0.45	0.25
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8.0		8.0			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0			0.10	0.60	0.30
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0		1.0			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	1.0				
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1.0	1.0				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	0.80		0.20		
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	6.0		6.0			
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	91,466.0	2,213.0	16,672.0	5,237.0	47,425.0	19,919.0

* SPECIALTY ITEM

* D5 CRACK & JOINT SEAL 2011-1
** MCLEAN, DEWITT, & PIATT

FILE NAME : c:\pw\work\pwidot\bucklesj\0252724\050880-sht-cover.dgn	USER NAME : bucklesjj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	**		33	11
		PLOT SCALE : 40.0000 / IN.	CHECKED -		REVISED -				CONTRACT NO. 70880			
		PLOT DATE : 2/3/2011	DATE -		REVISED -	ILLINOIS FED. AID PROJECT						