

# GENERAL NOTES

G.N.-100: ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-100A: ELECTRONIC FILES AND/OR ELECTRONIC SURVEY INFORMATION INCLUDING CADD FILES WILL NOT BE AVAILABLE TO THE CONTRACTOR.

G.N.-451 (SPECIAL): AN APPLICATION RATE OF 0.41 POUNDS/FOOT WAS USED TO DETERMINE THE FIBER ASPHALT QUANTITY.

G.N.-703A: SHORT TERM PAVEMENT MARKING SHALL BE APPLIED TO THE PAVEMENT AFTER ANY OF THE FOLLOWING: COLD MILLING AND/OR PLACING BITUMINOUS MATERIALS (PRIME COAT), LEVELING BINDER (MACHINE METHOD), BINDER AND SURFACE COURSES. SHORT TERM PAVEMENT MARKING PLACED ON THE SURFACE, SHALL COINCIDE WITH THE FINAL PAVEMENT STRIPING. SHORT TERM PAVEMENT MARKINGS PLACED PRIOR TO THE SURFACE SHALL COINCIDE WITH THE EXISTING PAVEMENT MARKINGS. USE 4 FEET PER 40 FEET (OR 10% PER STATION).

G.N.-703 (SPECIAL): PAINT WILL NOT BE ALLOWED TO BE USED FOR SHORT TERM PAVEMENT MARKINGS AND TEMPORARY PAVEMENT MARKINGS. PAVEMENT MARKING TAPE SHALL BE USED AT ALL LOCATIONS WHERE WORK ZONE PAVEMENT MARKINGS ARE CALLED OUT IN THE PLANS. NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

G.N.-781: RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED IN ACCORDANCE WITH STANDARD 781001, AND THE DETAILS SHOWN IN THE PLANS. IF THERE IS ANY DISCREPANCY BETWEEN THE STANDARD AND THE DETAILS IN THE PLANS, THE DETAILS IN THE PLANS SHALL GOVERN. THE FINAL PAVEMENT MARKINGS SHALL BE IN PLACE PRIOR TO PLACING THE RAISED REFLECTIVE PAVEMENT MARKERS AND THE RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED MIDWAY IN THE 30 FOOT (9m) SPACE BETWEEN THE DASHED CENTERLINE STRIPES (WHEN APPLICABLE).

NO COMMITMENTS

▲ REVISIED SHEET 4/13/11

• 693 & 704

\*\* (129)-2 & (1,2) & (FAP 10)

FILE NAME =	USER NAME = ceerlockbm	DESIGNED - BMC	REVISED 4-5-2011	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pavidot\ceerlockbm\0243284\	678692-sht-gennote.dgn	DRAWN - BMC	REVISED -					*	**	MCLEAN	55	04
	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -			SCALE: N/A	SHEET NO. 1 OF 1 SHEETS	STA. -	TO STA. -	CONTRACT NO. 70892		
	PLOT DATE = 4/7/2011	DATE - 12-22-10	REVISED -			<small>ILLINOIS FED. AID PROJECT</small>						